


Trustees of Bloomington Schools
D.R. 128 Pg. 619



DESCRIPTION FOR
PARRISH BOUNDARY
JOB NUMBER 1645

A part of the northeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:
BEGINNING at a point which is 433.11 feet north and 35.00 feet west of the southeast corner of the said quarter Section; thence SOUTH 89 degrees 52 minutes 36 seconds WEST 18.90 feet; thence SOUTH 03 degrees 40 minutes 27 seconds WEST 170.78 feet to the north right-of-way line of State Road 46; thence along said right-of-way line SOUTH 49 degrees 20 minutes 30 seconds WEST 63.25 feet; thence NORTH 86 degrees 20 minutes 20 seconds WEST 319.94 feet to a point on a curve concave to the south and having a tangent of 400.03 feet and a radius of 22,918.31 feet thence on a chord bearing NORTH 85 degrees 55 minutes 07 seconds WEST 413.28 feet to the east line of a tract as recorded in Deed Record 125, pages 619, in the office of the Recorder of Monroe County, Indiana; thence leaving said right-of-way and curve and along said line NORTH 00 degrees 17 minutes 37 seconds EAST 416.81 feet; thence leaving said line SOUTH 89 degrees 32 minutes 33 seconds EAST 183.90 feet; thence SOUTH 00 degrees 17 minutes 37 seconds WEST 10.00 feet; thence SOUTH 89 degrees 07 minutes 36 seconds EAST 623.44 feet; thence SOUTH 00 degrees 00 minutes 00 seconds WEST 234.00 feet to the point of beginning, containing 7.871 acres, more or less.

EXCEPTING THEREFROM, a part of the northeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:
BEGINNING at a point which is 519.17 feet north and 101.43 feet west of the southeast corner of the said quarter Section; thence NORTH 89 degrees 07 minutes 37 seconds WEST 116.00 feet to a non-tangent curve to the right, the radius of which bears NORTH 02 degrees 38 minutes 17 seconds EAST 20.00 feet; thence northwesterly through a central angle of 58 degrees 15 minutes 59 seconds along said curve 20.34 feet; thence NORTH 00 degrees 52 minutes 24 seconds EAST 52.00 feet to a tangent curve to the right having a radius of 40.00 feet; thence through a central angle of 20 degrees 29 minutes 14 seconds along said curve 14.30 feet; thence SOUTH 89 degrees 07 minutes 37 seconds EAST 130.18 feet; thence SOUTH 00 degrees 52 minutes 24 seconds WEST 76.00 feet to the point of beginning, containing 0.23 acres, more or less. Containing in all after said exception, 7.641 acres, more or less.

Standards observed and used on this project conform to Minimum Standard Detail Requirements for Indiana Land Title Surveys as adopted January 16, 1970, by Indiana Society of Professional Land Surveyors and as endorsed October 27, 1970, by the Indiana Land Title Association.
Easements located as per Lloyds Title Insurance Corporation, Title Commitment Number 86620415, dated June 4, 1992.

Subject to the above conditions and restrictions, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control, and that all information shown is true and correct to the best of my knowledge and belief.

Certified to this _____ day of June, 1992.

Don E. Bledsoe
Registered Land Surveyor No. S0559
State of Indiana



SURVEYOR'S REPORT FOR
PARRISH BOUNDARY
JOB NUMBER 1645

1). In accordance with Title 864, Article 1.1, Chapter 13, Section 1 through 34 of the Indiana Administrative Code, the following observations and opinions are submitted regarding the various uncertainties in the locations of the lines and corners established on this survey as a result of:

- a). **Variances** in the reference monuments,
- b). **Discrepancies** in the record descriptions and plans,
- c). **Inconsistencies** in lines of occupation and,
- d). **Random Errors** in Measurement Theoretical Uncertainty.

The theoretical uncertainty (due to random errors in measurement) of the corner of the subject tract established in this survey is written specifications for a Class B survey (0.25) feet as defined in I.A.C. 864.

This survey was performed at the request of Marsh Supermarkets Inc.

This tract was previously surveyed in May of 1984 by Smith Quillman Associates, Inc. The corners of the previous survey were found. The only changes to the previous survey were as follows:

- 1) The north boundary line was moved 50.00 feet north to include Parrish road which has been conveyed back to Parrish.
- 2) A portion of Deed Record 93, page 245, has been added at the northwest corner of the property. The north line of this tract was set at a location determined by the client.

As a result of the above observations, it is my opinion that the uncertainties of the locations of lines and corners established on this survey are as follows:

- Due to **discrepancies** in record descriptions: none.
- Due to **inconsistencies** in lines of occupation: none.
- Due to **variances** in reference monuments: 2.95 feet.

Smith Quillman Associates, Inc.
3625 Morrisville Drive
Bloomington, Indiana 47402
Telephone: 812.336.6536
Fax: 812.336.6536
Telex: 317.841.9102

CERTIFIED

PARRISH
LAND TITLE
SURVEY

REVISIONS	BY	DATE

DESIGNED	DRAWN	CHECKED	DATE

JOB NUMBER
1645

SHEET
1

OF
1

DATE: "LTS"

LAND
TITLE
SURVEY

LAND TITLE SURVEY

PART OF THE SOUTHEAST QUARTER
OF SECTION 29, T9N, R1W
MONROE CO., IN.

DESCRIPTION

Job #0514

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

Commencing at a P.K. nail marking the Northeast corner of said Southeast quarter; thence SOUTH 00 degrees 01 minutes 01 seconds EAST, 469.10 feet to a P.K. nail in the centerline of Kinser Pike and Gourley Pike; thence NORTH 89 degrees 04 minutes 53 seconds WEST, 260.36 feet to a P.K. nail and the point of beginning; thence NORTH 00 degrees 01 minutes 00 seconds WEST, 406.83 feet to a 5/8" rebar; thence NORTH 85 degrees 50 minutes 00 seconds WEST, 25.40 feet to a 5/8" rebar and a point on a non-tangent curve having a radius of 22,766.31 feet and subtended by a long chord bearing a non-tangent curve 09 minutes 39 seconds WEST, 250.36 feet; thence Northwesterly along said curve 250.37 feet to an iron pipe; thence SOUTH 00 degrees 01 minutes 10 seconds EAST, 421.51 feet to a railroad spike in the centerline of Gourley Pike; thence SOUTH 89 degrees 04 minutes 53 seconds EAST, 285.12 feet to the point of beginning, containing 2.71 acres, more or less.

Easements shown are per Tior Title Insurance Company, Title Commitment Number 5087-0017, dated December 9, 1987.

Standards observed and used on this project conform to Minimum Standard Detail Requirements for Indiana Land Title Surveys as adopted January 16, 1970 by the Indiana Society of Professional Land Surveyors and as endorsed October 27, 1970 by the Indiana Land Title Association.

I hereby certify to Joe Harrell and that the survey work performed on the project shown herein was performed either by me or under my direct supervision and control, and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 20th day of September, 1994.

Ben E. Bledsoe
Ben E. Bledsoe
Registered Land Surveyor No. 90559
State of Indiana

REPORT OF SURVEY

#0514

In accordance with Title 864, Article 1.1, Chapter 13, Section 1 through 34 of the Indiana Administrative Code, the following observations and opinions are submitted regarding the various uncertainties in the locations of the lines and corners established on this survey as a result of:

- Variances in the reference monuments;
- Discrepancies in record descriptions and plat;
- Inconsistencies in lines of occupation and;
- Random Errors in Measurement (Theoretical Uncertainty);

The Theoretical Uncertainty (due to random errors in measurement) of the corners of the subject tract established this survey is within the specifications for a Class B Survey (0.25 feet) as defined in IAC 864.

This survey was prepared at the request of Joe Harrell. The property is currently in the name of Greene and Harrell Mortuary, Inc. (Deed Record 383, page 461).

Corners Found:

- Northeast corner, Southeast quarter; P.K. nail.
- Northwest corner, WGT Partnership (Deed Record 407, page 208); Smith Gullman rebar.
- Southwest corner, WGT Partnership (Deed Record 407, page 208); P.K. nail.
- Northwest corner, Greene and Harrell (Deed Record 383, page 461); 1" iron pipe.
- Northwest corner of Colonial Crest Apartments; iron pipe found.
- Northeast corner Kinser Square Condom P.K. nail.

Establishment of Lines and Corners:

The corners (2) and (3) of the WGT property were held as good. The distance along Gourley Pike to Kinser Pike (5) to (3) checked with record, 427.88 feet.

The distance from the street intersection to the Northeast corner of the Southeast quarter (6) to (1) was 469.10 measured versus 472.00 feet record.

The iron pipe at the Northwest corner of the subject property was within 0.40 feet of record.

The Southwest corner of the property was set at record from the P.K. at the intersection of Gourley Pike and Kinser Pike.

Subject to the above observations, it is my opinion that the uncertainties in the location of the lines and corners established on this survey are as follows:

Due to variances in reference monuments; 2.90 feet North-South due to section corner location.

Due to discrepancies in the record description; none.

Due to inconsistencies on lines of occupation; none.

NOTE:
PER COMMUNITY-PANEL NUMBER 180169-0025-C
THIS PROPERTY IS NOT IN FLOOD HAZARD AREA


0 10 20 30 40
SCALE 1"=20'

H.H.GREGG
STORE

WGT LIMITED
PARTNERSHIP
(407/208)

LEGEND

WATER
SANITARY
TELEPHONE
OHE
UGR
GAS
FIRE HYD
POWER POLE





TOP OF CASTING OF A SANITARY MANHOLE
4'-51.00" WEST OF SOUTH EAST CORNER
OF PROPERTY, AND IN THE CENTER OF
GOURLEY PIKE.
ELEV.= 764.06

P/K NAIL (FD)
NORTH EAST CORNER
SOUTHEAST QUARTER
SECTION 29
T9N, R1W

P/K NAIL (FD)

Revisions	By	Date	Bledsoe Tapp & Co., Inc.	
			359 Landmark Avenue Bloomington, IN 47404 (812) 336-8277	
			LAND TITLE SURVEY	
			JOE HARRELL	
			DESIGNED BY:	1 OF 1
			DRAWN BY: JDS	
			CHECKED BY: BEB	
			DATE 09-28-94	JOB# 514



FILED
JAN 23 1987
Rodney J. Brown
Surveyor Monroe County, Indiana

SURVEY PLAT
OF
MARATHON PETROLEUM CO. PROPERTY
LOCATED IN SEC. 29, T.9N., R.1W., SECOND P.M.
MONROE COUNTY, INDIANA

SURVEYOR'S CERTIFICATION

I, JAMES C. BENNETT, hereby certify that I am a Land Surveyor licensed in accordance with the Laws of the State of Indiana and that this drawing represents a survey completed under my supervision on 7-13-85. I also certify that all physical features exist as shown to the best of my knowledge.

James C. Bennett 7-17-85
Indiana License # 50438 Date



21 FEB. 86 CORBIN

Bloomington, Ind.


#2460

Exhibit "A"

BEYERS

Bligh Trip

Dec 89.00.00



DESCRIPTION:

A part of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at the Southeast corner of Lot No. 1 of Block No. 1 in Arlington Place; said being a subdivision of a part of said Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, thence running South 89 degrees 14 minutes 40 seconds East for 252.00 feet, thence South 01 degree 19 minutes East for 170.00 feet, thence North 89 degrees 14 minutes 40 seconds West for 773.23 feet and to the right-of-way of State Road No. 46, thence running with said right-of-way North 25 degrees 41 minutes 04 seconds West for 89.85 feet, thence leaving said right-of-way and running North 76 degrees 40 minutes 25 seconds East for 152.10 feet, thence South 89 degrees 14 minutes 40 seconds East for 101.05 feet, thence North 02 degrees 46 minutes 57 seconds West for 152.68 feet thence South 89 degrees 14 minutes 15 seconds East for 312.32 feet, thence South 01 degree 19 minutes East for 100.00 feet and to the point of beginning. Containing in all 3.48 acres, more or less.



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
June 22, 1984

FILED

JUL 18 1984

W. Simpson
Auditor Monroe County, Indiana

FILED

JAN 23 1987

Rodney J. Brown

Surveyor Monroe County, Indiana

2.208 ACRES

**SURVEY PLAT
OF
MARATHON PETROLEUM CO. PROPERTY
LOCATED IN SEC. 29, T.9N., R.1W., SECOND P.M.
MONROE COUNTY, INDIANA**

SURVEYOR'S CERTIFICATION

I, JAMES C. BENNETT, hereby certify that I am a Land Surveyor licensed in accordance with the Laws of the State of Indiana and that this drawing represents a survey completed under my supervision on 7-13-85. I also certify that all physical features exist as shown to the best of my knowledge.



James C. Bennett 7-17-85
Indiana License # 50438 Date



Bloomington, Ind

1120600

EXHIBIT-B



SCALE: 1"=40'




(812) 334-8941
682 Green Road
Bloomington, IN 47401
res. (812) 339-6541

SURVEYOR LOCATION REPORT

THIS REPORT IS BASED ON LIMITED ACCURACY DATA AND THEREFORE NO DATA HEREIN SHOULD BE USED FOR CONSTRUCTION OR ESTABLISHING BOUNDARY OR FENCE LINES.

PROPERTY ADDRESS: Section 29, Township 9 North, Range 1 West
PROPERTY DESCRIPTION: See Below



Part of the East Half of the Southwest Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana and more particularly described as follows: Beginning North Zero (00) Degrees, Forty-seven (47) Minutes, Twenty-one (21) Seconds West 1888.06 feet from a PK Nail found marking the Southwest Corner of said East Half, thence continuing North Zero (00) Degrees, Forty-seven (47) Minutes, Twenty-one (21) Seconds West 80.00 feet to a rebar set, thence North Eighty-eight (88) Degrees, Three (03) Minutes, Ten (10) Seconds East 424.77 feet to a rebar set on the West Right-of-Way Line of State Road 46, thence along said Right-of-Way Line South Nine (09) Degrees, Forty-four (44) Minutes, Nineteen (19) Seconds East 80.73 feet to a rebar set, thence South Eighty-eight (88) Degrees, Three (03) Minutes, Ten (10) Seconds West 437.33 feet to the Point of Beginning. Containing 0.79 Acres, more or less

* This property is not located in a Flood Hazard Area.

DESIGNATED PARTIES

MORTGAGEE
OR ASSIGNEES:
TITLE CO.:
OTHER:

REFERENCE NO.

REFERENCE NO.

I, the undersigned, an Indiana Registered Land Surveyor, hereby certify that on the date shown, I supervised the inspection of the real estate described herein at the Address indicated. **THIS LOCATION REPORT WAS PREPARED FOR USE BY THE DESIGNATED PARTIES ONLY AND FOR NO ONE ELSE. THE ACCURACY OF THE LOCATION DATA SHOWN IS LIMITED TO THAT REQUIRED BY THE INDIANA "SURVEYOR LOCATION REPORT" MINIMUM REQUIREMENTS UNLESS OTHERWISE SPECIFIED AND EXPLAINED ON THIS DOCUMENT. IF A MORE ACCURATE OR DETAILED LAND SURVEY IS DESIRED OR IF CORNER MONUMENTS ARE REQUIRED, AN INDIANA LAND TITLE SURVEY SHOULD BE ORDERED.**

I further certify that to the best of my knowledge this Location Report conforms with the **SURVEYOR LOCATION REPORT** Minimum Requirements, as adopted by the Indiana Society of Professional Land Surveyors, Inc., on January 29, 1981, and approved by the Title Underwriters of Indiana, Inc., on March 20, 1981.

CERTIFICATION DATE 9/25/87

SURVEYORS SIGNATURE Steven W. Archer

SURVEYORS JOB NO.



SEAL



(812) 334-8941

682 Green Road
Bloomington, IN 47401
res. (812) 339-6541

LAND SURVEYING

LEGAL DESCRIPTION

Part of the East Half of the Southwest Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana more particularly described as follows:


Beginning North Zero (00) Degrees, Forty-seven (47) Minutes, Twenty-one (21) Seconds West 1888.06 feet from a PK Nail Found marking the Southwest Corner of said East Half, thence continuing North Zero (00) Degrees, Forty-seven (47) Minutes, Twenty-one (21) Seconds West 80.00 feet to a rebar set, thence North Eighty-eight (88) Degrees, Three (03) Minutes, Ten (10) Seconds East 424.77 feet to a reabr set on the West Right-of-Way Line of State Road 46, thence along said Right-of-Way Line South Nine (09) Degrees, Forty-four (44) Minutes, Nineteen (19) Seconds East 80.73 feet to a rebar set, thence South Eighty-eight (88) Degrees, Three (03) Minutes, Ten (10) Seconds West 437.33 feet to the Point of Beginning.

Containing 0.79 Acres, more or less.


SURVEYOR'S NOTE: The above description is the same tract of land described in a Warranty Deed recorded in Deed Book 298, page 267 in the office of the Recorder of Monroe County, Indiana. I have described the property from a Section Corner established by survey rather than from the Lot Corner in Ward's Addition to the Town of Chandlersville as in the original legal description because there is little evidence remaining in Ward's Addition from which to establish the original Lot Corners.



(812) 334-8941
682 Green Road
Bloomington, IN 47401
res (812) 339-6541



I, Steven W. Archer, hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana and that this plat and legal description correctly represents a survey completed by me on September 24, 1987 and that all monuments shown thereon actually exist and are to the best of my knowledge and belief accurately shown.



Steven W. Archer
Steven W. Archer
IN. Reg. No. 870009

BARNHART, STURGEON & SPENCER

ATTORNEYS AT LAW
313 NORTH LINCOLN STREET
P. O. BOX 1234

BLOOMINGTON, INDIANA 47402-1234

ALFRED EVENS (1935-1949)
LEROY BAKER (1935-1989)

FRANK A. BARNHART
SUZANNE STURGEON
MICHAEL J. SPENCER

ROBERT L. RALSTON
OF COUNSEL

TELEPHONE
(812) 332-9476

FAX #
(812) 331-8819

M E M O R A N D U M

To: Auditor of Monroe County, Indiana

Re: Parrish Addition

Date: September 10, 1992

This memo is being written to help reconcile differences in the records of the Auditor's Office and those in the Recorder's office concerning the unrecorded plat of Parrish Addition.

- ✓ 1. Parrish Road (Part of Tract 43) was conveyed to Mundy Realty, Inc. on July 18, 1992, Book 402, Page 293, 294.
- ✓ 2. Lot 2 - correct (*Tract 64*)
3. Lot 3 (Part of Tract 43) Benjamin H. Parrish and Maxine Parrish - this is correct except that Tract 43 includes Parrish Road (see 1 above).
- ✓ 4. Lot 4 (Tract 68) Timothy H. Parrish - correct.
5. Lot 5 (Part of Tract 90) this lot was not conveyed to Timothy H. Parrish. It is owned by Benjamin H. and Maxine Parrish. It should not be part of Tract 90; it should have a separate tract number.
6. Lot 6 (Part of Tract 90) - correct.
7. Lot 7 (Part of Tract 43) - correct except see paragraphs 1 and 3 above.
8. Lot 8 (Part of Tract 43) correct except see paragraphs 1 and 3 above.

Summary

All of Parrish Addition has been conveyed to others, except Lots 2 through 8 remain in the family.

See 29
P
C
Parrish

Lot 2 - Stephen B. Parrish since 10/6/61 (Book 140, page 402) - .361 acres.

Lot 3 - Benjamin H. and Maxine Parrish - .361 acres.

Lot 4 - Timothy H. Parrish since 10/27/64 - .274 acres

Lot 5 - Benjamin H. and Maxine Parrish - .223 acres.

Lot 6 - Timothy H. Parrish since 2/7/72 (Book 209, page 529) - .301 acres.

Lot 7 - Benjamin H. and Maxine Parrish - .3 acres.


Lot 8 - Benjamin H. and Maxine Parrish - .303 acres.

In order to finance the relocation of houses from the area purchased by Mundy Realty, it is necessary that we proceed with transfer of the properties, first to the grandchildren, (for tax reasons) and, then to Parrish Properties, an Indiana Partnership. We would appreciate your assistance in getting the records corrected as soon as possible.

I will be available all next week to meet with you. I am enclosing a copy of the unrecorded plat of Parrish Addition, and, a copy of the survey of the lands recently conveyed to Mundy Realty.


Very truly yours,

BARNHART, STURGEON & SPENCER


Frank A. Barnhart

FAB/dw


Enclosure



Lat
9-10-11-12-13-14-15-16


17- 18- 19-

FISHER ABST,
FREEMAN "




- REBAR FOUND
- REBAR SET


Proposed



SCALE: 1" = 50'



W COR., SW 1/4,
EC. 29, T 9 N, R 1 W,
MONROE CO., IN.



November 29, 2004
Douglas R. Curry

- FND REBAR FOUND THIS SURVEY
- S REBAR w/CAP SET THIS SURVEY

Morris tracks

LOT 4A AND LOT 4B OF RESUBDIVISION
OF LOT 4 MORRIS SUBDIVISION
JOB NO. 500497

Sec 29

1/2


Sec 29

B. T.

Shaw, Robert V.

APR 13 1987

Robney & Brown
Monroe County, Indiana



PLAT OF SURVEY			
PT. NE 1/4 OF SECTION 29-7N-1W			
FOR:	SCALE:	GRAPH:	DATE:
D. G. HONLEY, INC.	1" = 100'	R. S. 1003	3/1/87
DATE:	APPROVED BY:	REVIEWED BY:	DATE:
4/1/87	Robert C. Shaw		

Robert C. Sipes, Registered Land Surveyor

*Ind. Reg. No. 9016
P.O. Box 5311*

*Phone (812) 333-2984
Bloomington, IN 47402*

Plat of Survey Continued:
For B. G. Hoadley Quarries, Inc.

March 1, 1987

Legal Description:


A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West Monroe County, Indiana, described as follows:

Beginning at a point on the West line of said quarter section, said point being North 01 degree 45 minutes 33 seconds West 360.50 feet distant from the Southwest corner of said Northeast quarter, said point also being on the North right-of-way line of State Road #46; thence on and along said North right-of-way line with the following courses and distances:

thence South 88 degrees 30 minutes 19 seconds East 190.20 feet;
thence South 82 degrees 47 minutes 41 seconds East 201.00 feet;
thence South 88 degrees 30 minutes 19 seconds East 450.00 feet;
thence North 50 degrees 18 minutes 12 seconds East 53.15 feet;
thence South 88 degrees 30 minutes 19 seconds East 64.71 feet to the Southwest corner of the Arlington School Tract as described and heretofore recorded in Deed Record Book 125, page 619; thence North 01 degree 45 minutes 33 seconds West 936.51 feet to the Northwest corner of a 5.00 acre Tract as heretofore conveyed to Robert and Ginger Miller and being recorded in Deed Record Book 329, pages 310 and 311; thence on and along the North line of said Miller Tract East 510.94 feet to a point on the West line of Cascades Addition; thence on and along said West line North 01 degree 13 minutes 58 seconds West 355.54 feet; thence West 1458.82 feet to a point on the West line of the aforesaid Northeast quarter section; thence on said West line South 01 degree 45 minutes 33 seconds East 1282.51 feet to the point of beginning, containing 32.48 cres, more or less.

Subject to an ingress and egress easement along a portion of the East side of the above described tract as heretofore granted to Robert and Ginger Miller and being recorded in Deed Record Book 329, pages 310 and 311.

Boundary Surveys, Subdivisions, Mortgage Surveys, Mapping





04 03:51p

BledsoeTapp&Riggert

812-336-0817

P.1



DESCRIPTION: (From Record Documents. No survey made)
A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows:
Commencing at the Southeast corner of the property deeded from Crum to Wentz Property Management in IN 2001000793 WAR, said corner described in deed as being 429 feet East and 338.15 feet North of the Southwest corner of the said quarter section; thence along the East line of said property North 00 degrees 00 minutes 00 seconds East 137.60 feet to the point of Beginning; thence leaving said East line North 74.68 feet; thence North 09 degrees 19 minutes 57 seconds West 31.81 feet; thence North 86 degrees 22 minutes 54 seconds West 187.22 feet to the West line of the said Wentz property; thence along said West line North 00 degrees 00 minutes 00 seconds West 510.94 feet to the North line of the said Wentz property; thence along said North line North 89 degrees 56 minutes 00 seconds East 267.00 feet; to the East line of the said Wentz Property; thence along said East line South 00 degrees 00 minutes 00 seconds East 558.66 feet to the point of beginning. Containing in all 3.24 acres.

[Signature]

C.D. Graham LS 9500014 IN
615 W. Kirkwood Av.
Bloomington, IN 47404
1/14/04


Bledsoe 29

013-23430-01


Blgtn. Sup.

Sec 29

JACK ABERRIN




Description:
A part of the Southeast quarter of Section 12,
Township 9 North, Range 1 West, Monroe County,
Indiana described as follows: Beginning at a
point that is 429.00 feet East and 338.15 feet
North of the Southwest corner of the said
Southeast quarter; thence North for 697.27 feet;
thence South 89 degrees 56 minutes West for
267.00 feet; thence South for 697.27 feet;
thence North 89 degrees 56 minutes East for
267.00 feet and to the point of beginning.
Containing in all 4.28 acres more or less.



Sec 29

PT. of BEGINNING E.A.S.T.
for 429.0' then 338.15'
NORTH from S.W. CORNER of
SE 1/4, SECT. 29, T9N, R1W



Engineer's Certification:
I hereby certify that this plat is a true and complete survey of the described
property, and further certify that all improvements are wholly within the boundaries
of said described property,

Raymond Graham
Raymond Graham
R P E 3409 Indiana
2215 N. Smith Pike
Bloomington, Ind.
May 27, 1977



(812) 334-8941

205 N. College Ave.
Suite 512
Bloomington, IN 47404

LAND SURVEYING


013-40760-00

SURVEYOR LOCATION REPORT

THIS REPORT IS DESIGNED FOR USE BY A TITLE INSURANCE COMPANY WITH RESEDENTIAL LOAN POLICIES. NO CORNER MARKERS WERE SET AND THE LOCATION DATA HEREIN IS BASED ON LIMITED ACCURACY MEASUREMENTS. THEREFORE, NO LIABILITY WILL BE ASSUMED FOR AND USE OF THIS DATA FOR CONSTRUCTION OF NEW IMPROVEMENTS OR FENCES.

PROPERTY ADDRESS: 2005 North Kinser Pike, Bloomington, Indiana 47404
PROPERTY DESCRIPTION: A part of the Northeast quarter of Section 29,
CLIENT I.D. NO.: Township 9 North, Range 1 West, being more particularly described as follows: Beginning at a point in the centerline of Kinser Pike, said point being 1,012.125 feet North of the Southeast corner of said Northeast quarter section; thence West 245.0 feet; thence North 120.0 feet; thence East 245.0 feet to a point in the centerline of said Kinser Pike; thence South on said centerline 120.0 feet to the point of beginning, containing 0.675 acre, more or less.

Subject tract is not located in a flood hazard area.



FILED

MAY 30 1997

Barbara W. Clark
Auditor Monroe County Indiana

TITLE CO.:


I HEREBY CERTIFY TO THE PARTIES NAMED ABOVE THAT THE REAL ESTATE DESCRIBED HEREIN WAS INSPECTED UNDER MY SUPERVISION ON THE DATE INDICATED AND THAT, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS REPORT CONFORMS WITH THE REQUIREMENTS CONTAINED IN SECTIONS 42 THROUGH 44 OF 864 IAC 1.1-13 FOR A SURVEYOR LOCATION REPORT. THE ACCURACY OF ANY FLOOD HAZARD STATEMENT SHOWN ON THIS REPORT IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP.

DATE OF SURVEY: 11/9/95


REGISTERED LAND SURVEYOR'S SIGNATURE:

PROPOSED BUYER:

PROPOSED LENDER:



PLAT OF SURVEY



DR 120, P. 350
G.A. & A.E.
Sieboldt

DR 255, P. 319
G. & A. Sieboldt

REVIEWED PLANS SHALL
REMAIN ON BUILDING SITE
DURING CONSTRUCTION.

REVIEWED PLANS SHALL
REMAIN ON BUILDING SITE
DURING CONSTRUCTION.

DR 367, P. 378
M.C. & D.M. Rogers 2/3
M.S. Witkiewicz 1/3

LEGEND
 ◎ FOUND DRILL STEEL
 ◎ SET 1/2" DIA. REBAR
 • SET P.K. NAIL

SCALE
1" = 50'

10/12/13 DEED DESC.

MORRIS, DONETTA S. & JAMES
DR 335 P. 334

S89° 54' 20" E

IRON PW
SET

CHAIN LINK FENCE 321.74'

IRON PW
SET

MORRIS, DONETTA S. & JAMES
DR 335 P. 334

R.R. SPIKE FOUND
REF. AT CO. SURVEYOR'S OFF.

60' ROADWAY & UTILITY EASEMENT

CHAIN LINK FENCE
N0° 28' 26" E 412.79'

IRON PW
SET

705'
16' ELEC. EASEMENT
(DR 379 P. 451)

25' R/W


263'

CRESCENT RD.
N89° 23' 58" W 327.78'

SW CORNER,
SW 1/4, S29,
T9N, R1W

POINT OF
BEGINNING

SCALE: 1" = 60'



OVERHEAD POWER LINE

PUB. SERV. EASE. NO WIDTH RECORDED
(DR 335 P. 334)

415.69'
S00° 21' 33" E

IRON PW
SET

R.R. SPIKE
FOUND
REF. AT CO.
SURVEYOR'S OFF.

RALPH ROGERS & Co., INC.
DR 199 P. 315

be mfgd


DESCRIPTION

A part of the Southwest quarter of Section 29, Township 9 North, range 1 West, Monroe County, Indiana, described as follows: Commencing at a Rail road spike in the Southwest corner of said quarter section; thence running along the south line of said section South 89 degrees 23 minutes 58 seconds East for 337.94 feet and to the point of Beginning; thence leaving said section line and running North 00 degrees 28 minutes 26 seconds East for 412.79 feet to an iron pin; thence running South 89 degrees 54 minutes 20 seconds East for 321.74 feet to an iron pin; thence running South 00 degrees 21 minutes 33 seconds East for 415.69 feet and to a rail road spike in the said section line; thence along said section line North 89 degrees 23 minutes 58 seconds West for 327.78 feet and to the point of beginning. Containing in all 3.088 acres.

Subject to a 25 foot right of way along entire south side for Crescent Road.

Subject also to a Public Service Company Easement along the East side of subject property, as recorded in Deed Record 335, page 334, in the office of the recorder, Monroe County, Indiana.

Also subject to a 16 foot Electric easement as shown and recorded in Deed Record 379, page 451, in the office of the Recorder, Monroe County, Indiana.



Raymond Graham

Raymond Graham
IN LS 9978
3215 N. Smith Pike
Bloomington, Indiana
July 28, 1993

SURVEYOR'S REPORT (per 865 IAC 1-12 12)

A) Availability and condition of reference monuments:

- i. Rail road spike found 4 inches under pavement at the Southwest corner of Section 29,
referenced in the County Surveyor's office.
- ii. Rail road spike found 2 inches under pavement in the south line of Section 29 and being the Southeast corner of parent tract, referenced in the County Surveyor's office.
- iii. 6 inch by 6 inch limestone monument with brass cap marked 'Indiana Limestone Co. 1929' found in the Northeast corner of Devitt property.

B) Occupation or possession lines:

- i. No conflicts with possessions lines to described boundaries noted.

C) No overlaps or gaps in record description with adjoiner descriptions found.

D) Theoretical uncertainty of measurements:

- i. Uncertainty due to Electronic Distance Measurments = .03 feet
- ii. Class of survey = Class C as found in IAC 865

Deed of parent tract found in Deed Record 335 page 334 in the office of the Recorder, Monroe County, Indiana.

CERTIFICATION

I certify that this survey was performed wholly under the direction of myself, a registered land surveyor in the State of Indiana, and to the best of my knowledge and belief was executed according to survey requirements in 865 IAC 1-12, and that there are no conflicts with this subdivision and the recorded deed for the parent tract.



Raymond Graham
Raymond Graham
IN LS 9978
3215 N. Smith Pike
Bloomington, Indiana
July 28, 1993

589°54'20"E

3/4" I.P. SET

284.20'

3/4" I.P. SET

DEVITT, DAVID A. & DOREEN
DR 386 P. 107

N00°22'30"W

409.81'

3/4" I.P. SET

N89°23'58"W

150.00'

6" x 6"
LIMESTONE
MONUMENT

DEVITT, DAVID A.
& DOREEN
DR 386 P. 107

3/4" I.P. SET

N00°19'30"E

150.00'

N00°19'30"E

150.00'

25' R/W

3/4" I.P. SET

3/4" I.P. SET

20.00'

CRESCENT RD


N89°23'58"W

107.94'

SW CORNER
SW 1/4, S29,
T9N, R1W

DESCRIPTION


A part of the Southwest quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a rail road spike in the Southwest corner of said section; thence running North 00 degrees 22 Minutes 30 seconds West for 409.81 feet to an iron pin; thence running South 89 degrees 54 minutes 20 seconds East for 284.20 feet to an iron pin; thence running South 00 degrees 28 minutes 26 seconds West for 412.26 feet and to a rail road spike in the south line of said section; thence running along said south line and the approximate centerline of Crescent road North 89 degrees 23 minutes 58 seconds West for 107.94 feet; thence leaving said section line and said road and running North 00 degrees 19 minutes 30 seconds East for 150.00 feet to a limestone monument; thence running North 89 degrees 23 minutes 58 seconds West for 150.00 feet to an iron pin; thence running South 00 degrees 19 minutes 30 seconds East for 150.00 feet and to the said section line and said road; thence running along said section line and said road N 89 degrees 23 minutes 58 seconds West for 20.00 feet and to the point of beginning. Containing in all 2.135 acres. Subject to a 25 foot right of way along Crescent Road.



Raymond Graham
Raymond Graham
IN LS 9978
3215 N. Smith Pike
Bloomington, Indiana
July 28, 1993
page 1 of 2 see attached
Surveyor's Report

MORRIS, DONETTA S. & JAMES
DR 335 P. 334

SCALE 1"=60'



blf-29

SURVEYOR'S REPORT (per 865 IAC 1-12 12)

A) Availability and condition of reference monuments:

- i. Rail road spike found 4 inches under pavement at the Southwest corner of Section 29,
referenced in the County Surveyor's office.
- ii. Rail road spike found 2 inches under pavement in the south line of Section 29 and being the Southeast corner of parent tract, referenced in the County Surveyor's office.
- iii. 6 inch by 6 inch limestone monument with brass cap marked 'Indiana Limestone Co. 1929' found in the Northeast corner of Devitt property.

B) Occupation or possession lines:

- i. No conflicts with possessions lines to described boundaries noted.

C) No overlaps or gaps in record description with adjoiner descriptions found.

D) Theoretical uncertainty of measurements:


- i. Uncertainty due to Electronic Distance Measurements = .03 feet
- ii. Class of survey = Class C as found in IAC 865



Deed of parent tract found in Deed Record 335 page 334 in the office of the Recorder, Monroe County, Indiana

CERTIFICATION

I certify that this survey was performed wholly under the direction of myself, a registered land surveyor in the State of Indiana, and to the best of my knowledge and belief was executed according to survey requirements in 865 IAC 1-12, and that there are no conflicts with this subdivision and the recorded deed for the parent tract.




Raymond Graham
IN LS 9978
3215 N. Smith Pike
Bloomington, Indiana
July 28, 1993



Indiana Bell Telephone Description

A part of the South half of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, more particularly described as follows, to-wit: Beginning at a point that is 846.57 feet East and 619.37 feet North of the South half mile post of said Section 29, thence North 416 feet, thence West 417.57 feet, thence South 416 feet, thence East 417.57 feet and to the point of beginning, containing in all 4.0 acres, more or less.

Roadway Description


A part of the South half of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, more particularly described as follows, to-wit: Beginning at a point that is 846.57 feet East of the South half mile post of Section 29, thence North 1035.37 feet, thence East 60 feet, thence South 1035.37 feet, thence West 60 feet and to the point of beginning, containing in all 1.43 acres, more or less.

I hereby Certify that the above is a true and correct plat of a survey made by me, and that the improvements are located as shown thereon and that said improvements are located entirely within said property.


Raymond Graham

RAYMOND GRAHAM, R.P.E. 8409 Indiana
August 23, 1969

Raymond Graham
R.P.E. 8409 Indiana
July 25, 1969



SOUTH ONE HALF MILE POST
SECT. 29, TWP. 9 NORTH, RANGE 1, WEST




TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305

See a Bloomington
Bennett, IL



I Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that this plat and attached description correctly represent a land survey completed under my supervision on July 29th, 1988; that all the monuments shown thereon actually exist; and that their location and type are to the best of my knowledge accurately shown.

Edmund O. Farkas
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

*Rumple, Iowa
+ Shirley*

*Dec 29
B. City*

EXHIBIT "A"

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305

LEGAL DESCRIPTION

A part of the Southeast Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning at a point 1133.57 feet Westerly from the Southeast corner of said Section (said point being on the East line of a 60' x 240' tract of land which was recorded in Deed Book 175, page 321 in the office of the Recorder of Monroe County, Indiana, and said point being described in the above mentioned Deed Book 175, page 321 as being 1541.76 feet East of the Southwest corner of the Southwest Quarter of the Southeast Quarter of said Section), said point being on the South line of said Section and on Highway No. 46, thence North Zero (00) Degrees, Forty-nine (49) Minutes, Thirteen (13) Seconds West 240.00 feet, thence North Eighty-nine (89) Degrees, Fifty-six (56) Minutes, Thirty-five (35) Seconds West 80.00 feet, thence South Zero (00) Degrees, Forty-nine (49) Minutes, Thirteen (13) Seconds East 240.00 feet to the aforementioned South line of said Section and Highway No. 46, thence along said South line and said highway South Eighty-nine (89) Degrees, Fifty-six (56) Minutes, Thirty-five (35) Seconds East 80.00 feet to the point of beginning.

Containing 0.44 acres, more or less.

(Cont'd.)

DULY ENTERED
FOR TAXATION

JUN 12 1987

Rodney J. Brown
Auditor, Monroe County, Indiana

*5
2
2
9*


1/2

EXHIBIT "A" (Cont'd.)

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305



I, Edmund O. Farkas, hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that this plat and the following description correctly represent a land survey completed under my supervision on June 9, 1987; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.



$\frac{1}{2}$ 

RETURN TO:

Meridian Title Corporation
401 W. 7th Street, Bloomington, IN 47404

Mail Tax Statements to:

1101 Whisnand Rd.
Bloomington IN 47408

Property Address:

1839 N. Kinser Pike
Bloomington, IN 47404

AUDITOR'S RECORD

Transfer No. _____

Taxing Unit _____

Date _____

Tax ID No. _____

013-34350.00 plat 91

WARRANTY DEED

THIS INDENTURE WITNESSETH

KINSER CROSSING LLP, an Indiana limited liability partnership

CONVEY(S) AND WARRANT(S) TO

C. RANDALL POWELL and KATHRYN A. POWELL, husband and wife, for Ten Dollars and other valuable consideration the receipt whereof is hereby acknowledged, the following described REAL ESTATE in Monroe County, in the State of Indiana, to wit:

A part of the northeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows: Beginning at a point which is 519.17 feet north and 101.43 feet west of the southeast corner of the said quarter Section; thence North 89 degrees 07 minutes 37 seconds West 116.00 feet to a non-tangent curve to the right, the radius of which bears North 02 degrees 38 minutes 17 seconds East 20.00 feet; thence northwesterly through a central angle of 58 degrees 15 minutes 59 seconds along said curve 20.34 feet; thence North 00 degrees 52 minutes 24 seconds East 52.00 feet to a tangent curve to the right having a radius of 40.00 feet; thence through a central angle of 20 degrees 29 minutes 14 seconds along said curve 14.30 feet; thence South 89 degrees 07 minutes 37 seconds East 130.18 feet; thence South 00 degrees 52 minutes 24 seconds West 76.00 feet to the point of beginning. Containing 0.23 acres, more or less.

Subject to taxes pro-rated to the date of closing.

Subject to covenants, restrictions and easements of record.

Subject to the terms, provisions and conditions of the Easements with Covenants and Restrictions Affecting Land by and between Mundy Realty, Inc., an Indiana corporation, and Kinser Crossing Partnership, an Indiana General Partnership, recorded July 23, 1992 in Deed Record 402 at page 310, in the Office of the Recorder of Monroe County, Indiana.

Grantor certifies that Grantor is successor to Kinser Crossing Partnership, Grantee in Warranty Deed recorded July 22, 1992 in Deed Record 402 at page 291, in the Office of the Recorder of Monroe County, Indiana; that all the partners of Kinser Crossing Partnership registered the Partnership as Kinser Crossing LLP, an Indiana limited liability partnership in November, 2001.

The undersigned person(s) executing this Deed on behalf of the Grantor represent and certify that they are duly appointed representatives or general partners of Grantor and have been fully empowered by the partnership agreement or other proper agreement by and between the general partners of Grantor, to execute and deliver this Deed, that Grantor has full capacity to convey the real estate described herein and that all necessary has full capacity to convey the real estate described herein and that all necessary action for the making of such conveyance has been taken and done.

IN WITNESS WHEREOF, the Grantor has executed this deed this 30th day of January, 2003.

KINSER CROSSING LLP

Eric C. Stolberg

By: Eric C. Stolberg, Partner

Page 1 of 2

DULY ENTERED
FOR TAXATION

FEB 4 2003

Barbara M. Clark
Auditor Monroe County, Indiana

2/2



ENGINEERING, INC.

BLOOMINGTON, INDIANA

P. O. BOX, 231

PHONE ED. 6-4025

PARRISH ADDITION DESCRIPTIONS

ROADWAY:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point six hundred sixty-nine and no tenths (669.0) feet North and thirty-five and no tenths (35.0) feet West of the Southeast corner of said Northeast quarter, running thence West a distance of 625.0 feet, thence running North a distance of 199.1 feet, thence running West a distance of 40.0 feet, thence running South a distance of 421.1 feet, thence running East a distance of 40.0 feet, thence running North a distance of 192.0 feet, thence running East a distance of 625.0 feet and to the west right of way of Kinser Pike, thence North 50.0 feet to the point of beginning.

Containing in all 1.081 acres.

Subject to all utility easements of record.

Lot # 3:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point eight hundred sixty-two and thirteen hundredths (862.13) feet North and three hundred ninety-seven and thirty-three hundredths (397.33) feet West of the Southeast corner of said Northeast quarter running thence South a distance of 193.1 feet and to a drive, thence running West a distance of 81.33 feet, thence running North a distance of 193.1 feet, thence running East a distance of 81.33 feet and to the point of beginning.

Containing in all .361 acres.

Subject to all utility easements of record.

Lot # 4:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point eight hundred sixty-two and thirteen hundredths (862.13) feet North and four hundred seventy-eight and sixty-six hundredths (478.66) feet West of the Southeast corner of said Northeast quarter, running thence South a distance of 193.1 feet and to a drive, thence running West a distance of 81.33 feet, thence running North a distance of 193.1 feet, thence running N41°09'E a distance of 123.62 feet and to the point of beginning.

Containing in all .274 acres.

Subject to all utility easements of record.

Lot # 5:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point six hundred sixty-nine and no tenths (669.0) feet North and five hundred sixty and no tenths (560.0) feet West of the Southeast corner of said Northeast quarter, said point being on the North right of way of a drive, running thence West a distance of 100.0 feet, thence running North a distance of 100.0 feet, thence running East a distance of 100.0 feet, thence running South a distance of 100.0 feet and to the point of beginning.

Containing in all .223 acres.

Subject to all utility easements of record.

5-10-78-9 (10) 12

Sec 29-9-1W



ENGINEERING, INC.

BLOOMINGTON, INDIANA

P. O. BOX, 231

PHONE ED. 8-4028

FARRISH ADDITION DESCRIPTIONS

Lot # 6:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point eight hundred sixty-two and thirteen hundredths (862.13) feet North and six hundred sixty and no tenths (660.0) feet West of the Southeast corner of said Northeast quarter, said point being on the east right of way of a drive, running thence east a distance of 181.33 feet, thence running S41°09'W a distance of 123.62 feet, thence running West a distance of 100.0 feet and to the east right of way of a drive, thence running North a distance of 92.1 feet and to the point of beginning.

Containing in all .301 acres.

Subject to all utility easements of record.

Lot # 7:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point eight hundred sixty-two and thirteen hundredths (862.13) feet North and seven hundred and no tenths (700.0) feet West of the Southeast corner of said Northeast quarter, said point being on the west right of way of a drive running thence West a distance of 143.6 feet, thence running South a distance of 91.1 feet, thence running east a distance of 143.6 feet, thence running North a distance of 91.1 feet and to the point of beginning.

Containing in all .300 acres.

Subject to all utility easements of record.

Lot # 8:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point seven hundred seventy-one and no hundredths (771.0) feet North and seven hundred and no tenths (700.0) feet West of the Southeast corner of said Northeast quarter, said point being on the west right of way of a drive, running thence West a distance of 143.6 feet, thence running South a distance of 92.0 feet, thence running East a distance of 143.6 feet, thence running North a distance of 92.0 feet and to the point of beginning.

Containing in all .303 acres.

Subject to all utility easements of record.

Lot # 9:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point six hundred seventy-nine and no tenths (679.0) feet North and seven hundred and no tenths (700.0) feet West of the Southeast corner of said Northeast quarter, said point being on the west right of way of a drive, running thence West a distance of 143.6 feet, thence running South a distance of 86.0 feet, thence running East a distance of 143.6 feet, thence running North a distance of 86.0 feet and to the point of beginning.

Containing in all .288 acres.

Subject to all utility easements.

Lot # 10:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point five hundred sixty-three and no tenths (563.0) feet North and seven hundred and no tenths (700.0) feet West of the Southeast corner of said Northeast quarter, said point being on the west right of way of a drive, running thence West a distance of 143.6 feet, thence running South a distance of 80.0 feet, thence running East a distance of 143.6 feet, thence running North a distance of 80.0 feet and to the point of beginning.

Containing in all .264 acres.

Subject to all utility easements of record.



ENGINEERING, INC.

BLOOMINGTON, INDIANA

P. O. BOX, 231

PHONE ED. 6-4025

PARRISH ADDITION DESCRIPTIONS

Lot # 11:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point five hundred thirteen and no tenths (513.0) feet North and seven hundred and no tenths (700.0) feet West of the Southeast corner of said Northeast quarter, said point being on the west right of way of a drive, running thence West a distance of 143.6 feet, thence running South a distance of 80.0 feet, thence running East a distance of 143.6 feet, thence running North a distance of 80.0 feet and to the point of beginning.

Containing in all .264 acres.

Subject to all utility easements of record.

Lot # 12:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and six hundred sixty and no tenths (660.0) feet West of the Southeast corner of said Northeast quarter thence running North a distance of 86.0 feet, thence running East a distance of 100.0 feet, thence running S 42°56'E a distance of 117.46 feet, thence running West a distance of 180.0 feet and to the point of beginning.

Containing in all .276 acres.

Subject to all utility easements of record.

Lot # 13:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point five hundred nineteen and no tenths (519.0) feet North and six hundred sixty and no tenths (660.0) feet West of the Southeast corner of said Northeast quarter, said point being on the East right of way of a drive, running thence North a distance of 100.0 feet, thence running East a distance of 100.0 feet, thence running South a distance of 100.0 feet, thence running West a distance of 100.0 feet and to the point of beginning.

Containing in all .223 acres.

Subject to all utility easements of record.

Lot # 14:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and four hundred eighty and no tenths (480.0) feet West of the Southeast corner of said Northeast quarter running thence N 42°56'W a distance of 117.46 feet, thence running North a distance of 100.0 feet and to the south right of way of a drive, thence running East a distance of 80.0 feet, thence running South a distance of 186.0 feet and to the point of beginning.

Containing in all .263 acres.

Subject to all utility easements of record.

Lot # 15:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and four hundred and no tenths (400.0) feet West of the Southeast corner of said Northeast quarter running thence west a distance of 80.0 feet, thence running North a distance of 186.0 feet, thence running East a distance of 80.0 feet, thence running South a distance of 186.0 feet and to the point of beginning.

Containing in all .341 acres.

Subject to all utility easements of record.



ENGINEERING, INC.

BLOOMINGTON, INDIANA

P. O. BOX, 221

PHONE CO. 3-4088

PARRISH ADDITION DESCRIPTIONS

Lot # 16:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and three hundred twenty and no tenths (320.0) feet West of the Southeast corner of said Northeast quarter running thence West a distance of 80.0 feet, thence running North a distance of 186.0 feet, thence running East a distance of 80.0 feet, thence running South a distance of 186.0 feet and to the point of beginning.

Containing in all .341 acres.

Subject to all utility easements of record.

Lot # 17:

A part of the Northeast quarter of section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and two hundred forty and no tenths (240.0) feet West of the Southeast corner of said Northeast quarter running thence West a distance of 80.0 feet, thence running North a distance of 186.0 feet, thence running East a distance of 80.0 feet, thence running South a distance of 186.0 feet and to the point of beginning.

Containing in all .341 acres.

Subject to all utility easements of record.

Lot # 18 and 19:

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, 2nd PM, Monroe County, Indiana, bounded and described as follows, to wit:

Beginning at a point four hundred thirty-three and no tenths (433.0) feet North and thirty-five and no tenths (35.0) feet West of the Southeast corner of said Northeast quarter said point being on the west right of way of Kinser Pike, running thence West a distance of 205.0 feet, thence running North a distance of 186.0 feet, thence running East a distance of 205.0 feet and to the right of way of Kinser Pike, thence running South a distance of 205.0 feet and to the point of beginning.


Containing in all .876 acres.

Subject to all utility easements of record and easement of the Monroe County Commissioners.

The foregoing descriptions were written by me, a licensed Land Surveyor in the State of Indiana on September 15, 1964

Robert C. Mann
Robert C. Mann ILS #7867

Bloomington 29 (SS)



WILLIS WILEY-TRACTS

Tract #28

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1472.16 west and 620.65 feet south of the east half mile corner of the said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

Tract # 29

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1572.16 west and 620.65 feet south of the east half mile corner of said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

Tract # 30 *Myers*

also, A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1672.16 feet west and 620.65 feet south of the east half mile corner of section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

28

WILLIS WILEY*TRACTS

Tract # 25

A part of the northwest quarter of the southeast quarter of section 29-T9N;R1W-in Monroe County, Indiana. Beginning at a point that is 1172.16 feet west and 490.65 feet south of the east half mile corner of said section 29; thence running west for 200 feet; thence running south for 130 feet; thence running east for 200 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.60 acres, more or less.

Tract #24

to L & M

A part of the northwest quarter of the southeast quarter of section 29-T9N;R1W-in Monroe County, Indiana. Beginning at a point that is 1372.16 feet west and 490.65 feet south of the east half mile corner of said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

Tract # 23

T9N, R1W

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1172.16 feet west and 490.65 feet south of the east half mile corner of said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet and to the place of beginning. Containing in all 0.30 acres, more or less.

Tract #22 - *Nyers*

West

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1572.16 feet west and 490.65 feet south of the east half mile corner of said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

*dot # 21 - 1172.16 West 490.65 South ******

Tract # 26

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1172.16 feet west and 620.65 feet south of the east half mile corner of said section 29; thence running west for 200 feet; thence running south 130 feet; thence running east for 200 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.60 acres, more or less.

Tract # 27

A part of the northwest quarter of the southeast quarter of section 29-in Monroe County, Indiana. Beginning at a point that is 1372.16 feet west and 620.65 feet south of the east half mile corner of said section 29; thence running west for 100 feet; thence running south for 130 feet; thence running east for 100 feet; thence running north for 130 feet, and to the place of beginning. Containing in all 0.30 acres, more or less.

1372.16

Bledsoe Tapp & Riggert, Inc.

-Quality Land Surveying and Civil Engineering Services-


BEN E. BLEDSOE, L.S.
PHILIP O. TAPP, L.S.
WILLIAM S. RIGGERT, P.E.

359 Landmark Avenue
Bloomington, IN 47404
(812) 336-8277
(812) 384-1114
FAX: (812) 336-0817


EXHIBIT "A"

TRACT "A" AND TRACT "B"
BOTH BEING A PART OF
LOT 5, STONE LAKE PHASE I, SECT. III
PLAT CABINET "C", ENVELOPE 147
MONROE COUNTY, INDIANA

JOB #462



SCALE: 1"=60'



Bledsoe Tapp & Riggert, Inc.*-Quality Land Surveying and Civil Engineering Services-*

BEN E. BLEDSOE, I.S.
 PHILIP O. TAPP, I.S.
 WILLIAM S. RIGGERT, P.E.
 359 Landmark Avenue
 Bloomington, IN 47404
 (812)336-8277
 (812)336-1114
 FAX: (812)336-0817

**JOB #0462
 TRACT B
 A PART OF LOT 5
 STONE LAKE PHASE I, SECTION III**

A part of Lot 5 of Stone Lake, Phase I, Section III as shown on the plat thereof and recorded in Plat Cabinet "C", Envelope 147, in the Office of the Recorder and being a part of the Northeast Quarter of Section 29, Township 9 North, Range 1 West, all of which is in Monroe County, Indiana, being more particularly described as follows:

COMMENCING at the Southeast corner of Lot 5 of said Stone Lake, Phase I, Section III; thence NORTH 82 degrees 47 minutes 41 seconds WEST along the South line of said Lot 5, 74.75 feet to the point of beginning; thence NORTH 00 degrees 00 minutes 00 seconds EAST, 246.50 feet to the North line of said Lot 5; thence NORTH 90 degrees 00 minutes 00 seconds WEST, 91.69 feet to the Northwest corner of said Lot 5; thence SOUTH 00 degrees 00 minutes 00 seconds WEST along the West line of said Lot 5, 80.93 feet; thence SOUTH 88 degrees 30 minutes 19 seconds EAST, 10.00 feet; thence SOUTH 00 degrees 00 minutes 00 seconds WEST, 162.00 feet to the South line of said Lot 5; thence along said South line, SOUTH 88 degrees 30 minutes 19 seconds EAST, 70.00 feet; thence continuing along said south line, SOUTH 82 degrees 47 minutes 41 seconds EAST, 11.81 feet to the point of beginning, containing 0.477 acres, more or less.


Subject to all easements, restrictions, covenants and rights of way of record.


This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose.

Evidence of easements have not been located in the field and are not shown on this survey drawing.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 12th day of September, 1997.


 Philip O. Tapp
 Registered Land Surveyor No. LS80900014
 State of Indiana



Send tax statements to:

1815 S. Walnut
Bloomington IN 47401

TAX DUPLICATE NUMBER

012-11800-05

CORPORATE WARRANTY DEED

THIS INDENTURE WITNESSETH, That Stone Lake Corporation, a corporation organized and existing under the laws of the State of Indiana, CONVEYS AND WARRANTS to Stone Lake Corporation, an Indiana Corporation, for and in consideration of One Dollar (\$1.00) and other valuable consideration not herein expressed, the receipt whereof is hereby acknowledged, the following described Real Estate in Monroe County, in the State of Indiana, to-wit:

A part of Lot 5 of Stone Lake, Phase I, Section III as shown on the plat thereof and recorded in Plat Cabinet "C", Envelope 147, in the Office of the Recorder and being a part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, all of which is in Monroe County, Indiana, being more particularly described as follows: Beginning at the Southwest corner of Lot 5 of said Stone Lake, Phase I, Section III; thence South 88 degrees 30 minutes 19 seconds East along the South line of said Lot 5, 10.00 feet; thence North 00 degrees 00 minutes 00 seconds East 162.00 feet; thence North 88 degrees 30 minutes 19 seconds West 10.00 feet to the West line of said Lot 5; thence South 00 degrees 00 minutes 00 seconds West along the West line of said Lot 5, 162.00 feet to the point of beginning, containing 0.037 of an acre, more or less.

Subject to the November installment of the 1996 taxes due and payable in 1997 and all subsequent taxes.

Subject to all easements and restrictions of record.

Th
sep
un-
I,
un-
sul
jur

TOWNSHIP: *BT.*

PARCEL NO.

11800-05

TRANS FROM: *Stone Lake Corporation*

LEGAL DESC: *Stone Lake Ph 1 Sec 3 Pt Lot 5*

VALUE, LAND:

IMPROVEMENTS:

TRANS TO: *Stone Lake Corporation*

ADDRESS: *1815 S Walnut*

add to 47401 #11800-06

LEGAL DESC: *Stone Lake Ph 1 Sec 3 Pt Lot 5 (.037A)*

VALUE, LAND:

IMPROVEMENTS:

INSTRUMENT: *war*

DATED: *10-3-97*

DATE OF TRANS: *10-6-97*

TRANS BY: *Jan*

Ent.

Tr. Bk.

Comp.

Date

veyed as a
and zoning
lake Phase
d shall not
applicable
ity having

at he is the
Board of
to convey
conveyance

FOR TAXATION

OCT 6 1997


Barbara H. Clark
Auditor Monroe County, Indiana

Sec 29-9-1W

Breeden to May

Sec 29
11-16-77

Bloomington
John D. May from
Joy Breeden



Description:

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, bounded and described as follows, to-wit: Beginning at a point 28 rods and 10 feet South of the Northeast corner of said quarter section, said point being the center of a twenty foot street, or roadway, running thence West 151 feet, thence South 182-1/2 feet, to the center of a twenty-five foot street, or roadway thence East 151 feet, thence North 182-1/2 feet, to the place of beginning.

Also a part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, bounded and described as follows, to-wit: Beginning at a point 151 feet West of a point, 28 rods and 10 feet south of the Northeast corner of said quarter Section, thence West 144 feet to the center of an alley, thence south 182-1/2 feet, thence east 144 feet, thence North 182-1/2 feet to the place of beginning.


Subject to a 7.50 foot easement for the Alley described as follows: beginning at the Northwest corner of this lot 28 rods 10 feet South and 295 feet West of the Northeast corner of said quarter Section, Thence South for 182.50 feet, Thence East for 7.50 feet, thence North for 182.50 feet, thence West for 7.50 feet and to the point of beginning.



Raymond Graham
Raymond Graham
R P R 8409 Indiana
3215 N. Smith Pike
Bloomington, Ind.
Sept. 29, 1977

REAL ESTATE TRANSFER
NOV 16 1977
John W. Davis
Auditor Monroe County, Ind.

Danbury Development to Court Development



DESCRIPTION:

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point that is 653.50 feet South of the Northeast corner of said quarter, said point being in Kinser Pike, thence running from said point and in said Kinser Pike South 01 degree 16 minutes 12 seconds East for 203.65 feet, thence leaving said road and running South 89 degrees 26 minutes 09 seconds West for 313.00 feet, thence South 04 degrees 50 minutes 48 seconds East for 185.46 feet, thence South 89 degrees 35 minutes West for 417.16 feet, thence North 01 degree 16 minutes 12 seconds West for 394.61 feet and to the centerline of a 25.00 foot street easement, thence running with said centerline East for 718.45 feet and to the point of beginning. Containing in all 5.16 acres, more or less. Subject to a 25.00 foot street easement from the centerline of Kinser Pike.



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
January 12, 1990

Sec 29

Sec 29-9-1W Nley to Runysle 1-8-79

RAYMOND GRAHAM


3215 N. SMITH PIKE
BLOOMINGTON, INDIANA 47401

R.P.E. 8409 INDIANA
June 10, 1978

Description:

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, in Monroe County, Indiana, described as follows: Beginning at a point that is 1155.00 feet West and 491.00 feet South of the Northeast corner of the Southeast quarter, said beginning point being on the South right-of-way of Cascades Avenue and marked by a 4-inch steel post; thence South 00 degrees 43 minutes East along an existing fence for 130.00 feet and to the true point of beginning. Thence South 00 degrees 43 minutes East along an existing fence for 474.40 feet to an existing fence corner; thence South 89 degrees 47 minutes 40 seconds West along an existing fence for 928.57 feet to an existing fence corner; thence North 01 degrees 04 minutes 20 seconds West for 491.08 feet; thence South 89 degrees 05 minutes East parallel to the South right-of-way of Cascades Avenue for 322.58 feet; thence South 00 degrees 43 minutes East for 130.00 feet; thence South 89 degrees 05 minutes East for 100.00 feet; thence North 00 degrees 43 minutes West for 130.00 feet, thence South 89 degrees 05 minutes East parallel to the South right-of-way of Cascades Avenue for 510.00 feet and to the true point of beginning. Containing in all 10.01 acres, more or less. Subject to an existing Electric Company Easement along the North side of the above described tract.

Raymond Graham
Raymond Graham
R.P.E. 8409 Indiana



FILED

JAN 8 1979

John W. Davis
Auditor Monroe County, Indiana

Cascade Ave

500°43'15"

474.40

130'

491' South
1/4 N-E corner
S-E 1/4, Sec. 18, T. 41N, R. 1W

539°05'E

510'

N 00°43' W

130'

100'

539°05'E

500°43'E

130'

539°05'E

322.58'

Antenna Road
Creek

491.08

N 01°02'20" W

10.01 A.

135'

928.57

539°47'40" W

392.48

344.60

FILED

JAN 8 1979

John W. Davis
Auditor Monroe County, Indiana

157.35

Property Description

Emro to M.P.C.

Gourley Rd. @ Kinser Pike
Bloomington, Indiana

Part of the SE 1/4 of Section 29, T9N, R1W, County of Monroe, State of Indiana, a tract of land bounded and described as follows:

Commencing at a point being the intersection of the centerline of Gourley Road with the east line of the SE 1/4 of said Section 29; said east line being also known as the centerline of Kinser Pike; thence, on and along said centerline of Gourley Road, N 89°05'14" W, a distance of 240.00 feet to the "True Point of Beginning: of the tract to be herein described.

Thence continuing along said centerline, N 89°05'14" W, a distance of 22.13 feet.

Thence N 00°01'00" W, a distance of 231.84 feet.

Thence S 89°05'14" E, a distance of 197.12 feet to the limited access right-of-way line of State Route No. 37.

Thence along said right-of-way line, S 12°41'49" E, a distance of 25.00 feet.

Thence N 89°05'14" W, a distance of 110.00 feet.

Thence S 37°37'01" W, a distance of 115.41 feet.

Thence S 00°01'00" E, a distance of 115.00 feet to the "True Point of Beginning" and containing 0.292 Acres of land, more or less, subject however to easements and rights-of-way of record.

This description has been prepared from deeds of record and a survey dated 7-13-85 by James C. Bennett, R.L.S. Indiana #S0438.

Edward A. Van Horn
Ohio R.L.S. #6563
12/16/86

22



SOUTH LINE
SE 1/4, SEC. 29, T9N, R1W

LEGAL DESCRIPTION – William K. Hanna and Wilma C. Hanna to
William K. Hanna Trucking, Inc.

Part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Bloomington Township, Monroe County, Indiana, being 10.00 feet of even width off of the West side of a parcel recorded in Deed Record 323, page 479, Office of the Recorder of Monroe County, Indiana, more particularly described as follows:


Commencing at the Southwest corner of said Southeast quarter; thence South 89 degrees 52 minutes 16 seconds East along the South line of said quarter section 1190.92 feet to the point of beginning; thence North 00 degrees 07 minutes 44 seconds East 30.00 feet; thence continuing North 00 degrees 07 minutes 44 seconds East 300.00 feet; thence South 89 degrees 52 minutes 16 seconds East 10.00 feet; thence South 00 degrees 07 minutes 44 seconds West 300.00 feet; thence continuing South 00 degrees 07 minutes 44 seconds West 30.00 feet to the South line of said Southeast quarter; thence North 89 degrees 52 minutes 16 seconds West along said South line 10.00 feet to the point of beginning, containing 0.076 acres, more or less.

Subject to a right-of-way for West 17th Street and to all other easements and rights-of-way of record.

Witness my hand and seal this 2ND
day of November, 1993.



Kevin B. Potter, L.S. No. S 0487
Bynum Fanyo and Associates, Inc.
700 North Walnut Street
Bloomington, Indiana 47404



CODE: 3249

PARCEL NO. 14

OWNER: MORRIS, DONETTA S. ET AL.

DRAWN BY: R.J. McCOOL 11-7-97

PROJECT NO. NH-062-4(008)

DEED RECORD 335, PAGE 334, DATED 05-08-87

CHECKED BY: D.K. ANDERSON 11-11-97

ROAD NO. : S.R. 46

DEED RECORD 413, PAGE 351, DATED 08-03-93

DEED RECORD 413, PAGE 353, DATED 08-03-93

DEED RECORD 426, PAGE 275, DATED 08-30-94

SCALE 1" = 400'

COUNTY : MONROE

SECTION : 29


TOWNSHIP : 9 N.

RANGE : 1 W.



HATCHED AREA IS THE APPROXIMATE TAKING

THIS PLAT WAS PREPARED FROM INFORMATION OBTAINED FROM THE RECORDER'S OFFICE AND OTHER SOURCES WHICH WERE NOT NECESSARILY CHECKED BY A FIELD SURVEY.
NOTE: CENTERLINE STATIONING IS METRIC.




Denise K. Anderson
11-11-97

TOTAL AREA = 20.457 AC.
R/W EXISTING = 0.034
NET TOTAL AREA = 20.423 AC.

A PART OF THE SOUTHEAST QUARTER OF
SECTION 29, TOWNSHIP 9 NORTH, RANGE 1 WEST
MONROE COUNTY, INDIANA

AREA FOR COUNTY
RECORDER



LOCATION MAP

NOTES:

PROJECT LOCATION

- 1) $\frac{5}{8}$ " Rebar will be set at all property corners.
- 2) Fieldwork completed August 2012.
- 3) Basis of bearing (Assumed).
- 4) Source of title Now or Formerly owned by Stephanie P., Wayne D. and Janet S. Nichols Instrument Number 2001023206 as found in the office of the Monroe County Recorder.
- 5) Reference is made to a survey performed by Eric Deckard for Comstock dated May 3rd, 2005.
- 6) Reference is made to the plat of Cascade Heights as found in Plat Cabinet "B", Envelope 58 in the office of the Monroe County Recorder.
- 7) Reference is made to a Location Control Route Survey performed by Jessica L. Stapleton dated May 21st, 2010 (Instrument Number 2010008858)
- 8) I affirm, under penalty for perjury, that I have taken responsible care to redact each Social Security Number in this document, unless required by law.
- ERIC L. DECKARD

LEGEND

- STONE FOUND
- UTILITY POLE
- REBAR FOUND
- REBAR SET
- CALCULATED
- RR SPIKE FOUND
- PIPE FOUND
- FENCE
- MAG SPIKE SET
- (R) RECORD
- (M) MEASURED

CERTIFICATION



The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.

Easements have been located in the field and prepared with this survey drawing. This qualification will be removed upon receipt and inspection of current title work.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of August, 2012.

Eric L. Deckard
Registered Surveyor LS29900012
State of Indiana



JANET & WAYNE NICHOLS

BOUNDARY SURVEY

DRAWN BY: AEW
DATED: 08/30/12

CHECKED BY:
ELD

SHEET
1 OF 4

SCALE
1"=40'



DECKARD LAND SURVEYING
1604 S. HENDERSON ST.
BLOOMINGTON IN. 47401
(812)961-0235

PROJECT NO.12-95

DECKARD LAND SURVEYING
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

**SURVEY DESCRIPTION FOR
JANET & WAYNE NICHOLS
JOB NO. 12-95**

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:


Commencing at the Northwest corner of the Southeast quarter of said Section 29; thence South 89 degrees 48 minutes 57 seconds East along the north line of said quarter for a distance of 719.46 feet to the Point of Beginning; thence leaving said north line North 02 degrees 22 minutes 14 seconds West for a distance of 7.41 feet to the centerline of W. Gourley Pike; thence along said centerline North 89 degrees 58 minutes 42 seconds East for a distance of 79.50 feet; thence leaving said centerline South 02 degrees 22 minutes 26 seconds East for a distance of 210.84 feet to a rebar set stamped "Deckard" on the north line of Cascade Heights Subdivision, passing through a rebar set stamped "Deckard" at 22.97 feet; thence South 89 degrees 44 minutes 47 seconds West along said north line for a distance of 79.50 feet to a ½ inch diameter rebar found; thence leaving said north line North 02 degrees 22 minutes 14 seconds West for a distance of 203.75 feet to the Point of Beginning, passing through a rebar set stamped "Deckard" at 181.04 feet, containing 0.38 acre, more or less.


Subject to the right-of-way of W. Gourley Pike and all legal easements record.

The within survey was performed without benefit of source of title and is subject to any statement of facts revealed by the same.


Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according to the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 30 day of August, 2012


ERIC L. DECKARD
Registered Land Surveyor No. 29900012
State of Indiana



Ac 29



502

 $\frac{1}{2}$

208 S. ROGERS

CORPORATE WARRANTY DEED

THIS INDENTURE WITNESSETH, That B. G. HOADLEY QUARRIES, INC.

_____, ("Grantor"), a corporation organized and existing under the laws of the State of Indiana, CONVEYS AND WARRANTS to ROBERT V. SHAW and NANCY SHAW HUSBAND AND WIFE

of Monroe County, in the State of Indiana, for the sum of One Dollars (\$1.00)

and other valuable consideration, the receipt of which is hereby acknowledged, the following described real estate in Monroe County, in the State of Indiana:

TRACT I

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point on the West line of said quarter section, said point being North 01 degree 45 minutes 33 seconds West 360.50 feet distant from the Southwest corner of said Northeast quarter, said point also being on the North right-of-way line of State Road #46; thence on and along said North right-of-way line with the following courses and distances: thence South 88 degrees 30 minutes 19 seconds East 190.20 feet; thence South 82 degrees 47 minutes 41 seconds East 201.00 feet; thence South 88 degrees 30 minutes 19 seconds East 450.00 feet; thence North 50 degrees 18 minutes 12 seconds East 53.15 feet; thence South 88 degrees 30 minutes 19 seconds East 64.71 feet to the Southwest corner of the Arlington School Tract as described and heretofore recorded in Deed Record Book 125, page 619; thence North 01 degree 45 minutes 33 seconds West 936.51 feet to the Northwest corner of a 5.00 acre tract as heretofore conveyed to Robert and Ginger Miller and being recorded in Deed Record Book 329, pages 310 and 311; thence on and along the North line of said Miller Tract East 510.94 feet to a point on the West line of Cascades Addition; thence on and along said West line North 01 degree 13 minutes 58 seconds West 355.54 feet; thence West 1458.82 feet to a point on the West line of the aforesaid Northeast quarter section; thence on said West line South 01 degree 45 minutes 33 seconds East 1282.51 feet to the point of beginning, containing 32.48 acres, more or less.

Subject to an ingress and egress easement along a portion of the East side of the above described tract as heretofore granted to Robert and Ginger Miller and being recorded in Deed Record Book 329, pages 310 and 311.

TRACT II

A part of the Northwest quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows: Commencing at the Southeast corner of said quarter section, thence on the East line of said quarter section North 01 degrees 45 minutes 33 seconds West 360.50 feet to the real point of beginning; thence continuing on said East line North 01 degrees 45 minutes 33 seconds West 955.51 feet to the Northeast corner of the Southeast quarter of said Northwest quarter section; thence on the North line of said quarter section West 477.47 feet; thence South 06 degrees 02 minutes 40 seconds East 288.27 feet; thence South 86 degrees 37 minutes 44 seconds West 253.96 feet; thence South 04 degrees 05 minutes 10 seconds East 637.21 feet to a point on the North right of way line of State Road No. 46; thence on and along said right of way line South 88 degrees 30 minutes 19 seconds East 684.80 feet to the point of beginning, containing 13.580 acres, more or less.

SUBJECT TO the first installment of real estate taxes for the year 1986, due and payable in May, 1987, and all subsequent taxes and assessments.

SUBJECT TO all easements, assessments, and legal rights-of-way of record.

There is no Indiana Gross Income tax due as a result of this conveyance.

Robert Shaw
208 S. Rogers

4-3-87

FILED
APR 13 1987

Rodney J. B. [Signature]
Recorder Monroe County, Indiana



(812) 334-8941

P. O. Box 1296
Bloomington, IN 47402

LAND SURVEYING

Client / Owner of Record
JoAnn Underwood




Basis of Bearings

rebar and cap marked Curry
found at the NE & SE corners
of Lot 41 Dyer 2nd Add. rotated
to Plat Bearing N 27 32' 36" E

Property Address: 1010 W. Orris Drive, Bloomington, Indiana 47404

Property Description:

Lot Number Forty-one (41) in Dyer Second Addition to the City of Bloomington, Indiana, as shown by the plat thereof, recorded in Plat Cabinet B, Envelope 127, in the Office of the Recorder of Monroe County, Indiana.



- 5/8" rebar w/cap set
- rebar found

I, Steven W. Archer, hereby certify that I am a Registered Land Surveyor, licensed with the Laws of the State of Indiana, and that the above plat and descriptions correctly represent a land survey performed by me or under my direct supervision and that the monuments shown thereon actually exist and are to the best of my knowledge and belief accurately shown
September 3rd, 2002

Steven W. Archer
Steven W. Archer
RLS 8700094



FILED
SEP 6 2002

Barbara W. Clark
Auditor Monroe County, Indiana



Plat 29



(812) 334-8941

682 Green Road
Bloomington, IN 47401
res. (812) 339-6541

LAND SURVEYING



1614 Arlington Road, Bloomington, Indiana 47401
Subject tract is not located in a flood hazard area.
See attached legal description

I, Steven W. Archer, hereby certify that I am a Registered

A part of Lots #2 and #3 of Block 1, Arlington Place Addition to the City of Bloomington, Monroe County, Indiana, more particularly described as follows:

Beginning at the Northwest corner of said Lot #3; thence South 88 degrees 59 minutes 13 seconds East along the north line of said Lot #3 a distance of 292.00 feet; thence South 01 degree 29 minutes 35 seconds East parallel with the east line of said Lot #3 a distance of 64.00 feet; thence South 72 degrees 20 minutes 03

seconds West 170.78 feet; thence North 89 degrees 54 minutes 01 second West 125.15 feet to the west line of said Lot #2; thence North 02 degrees 43 minutes 24 seconds West along the west line of Lots #2 and #3 a distance of 120.89 feet to the point of beginning, containing 0.69 acres, more or less.

SUBJECT TO a Right-of-way easement in favor of The Indianapolis Bloomington and Bedford Railroad Company, recorded in Deed Record 29, page 289, in the office of the Recorder of Monroe County, Indiana.

SUBJECT TO an Easement in favor of Joe D. Oliver and Dora Oliver dated December 2, 1954, recorded December 2, 1954, in Deed Record 116, page 349, a strip of land 5 feet wide extending eastward for a distance of 50 feet from the Southwest corner of the real estate hereinabove described and lying north and adjacent to the said 5 foot strip of land herein immediately described and said 5 foot strip of land being an extension of the 10 foot roadway hereinabove described and said 5 foot strip of land being used as a roadway.

SUBJECT TO all public highways and rights-of-way.

SUBJECT TO all conditions, restrictions, covenants, easements, and encumbrances as shown by the recorded plat of Arlington Place, recorded in Plat Book 3, pages 21-22, and Plat Book 3, page 112, in the office of the Recorder of Monroe County, Indiana.


SUBJECT TO an easement over and along a roadway Ten (10) feet wide, running in an easterly and westerly direction from the Bloomington-Ellettsville State Road #46 as a means of ingress and egress to and from the following described real estate, to-wit:

A part of Lot Number Three (3) in Block Number One (1), in Arlington Place, being a sub-division of a part of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, in Monroe County, Indiana, bounded and described as follows, to-wit: Beginning at a point on the North line of Lot Number Three (3) in Block Number One (1) in Arlington Place, which point is Two hundred Ninety-two (292) feet East of the Northwest corner of said Lot Number Three (3) (said beginning point being also the Northeast corner of a certain tract of land conveyed by Everett L. Richardson and Helen Richardson, husband and wife, to Mary Kirkman on the 29th day of September, 1952, said deed of conveyance being recorded on page 357 in Deed Record 112, of the records on file in the Recorder's office of Monroe County, Indiana); running thence South over and along the East line of said tract so conveyed by Richardsons to Kirkman and continuing south for a distance of One Hundred Fourteen (114) feet in all; running thence East to the East line of said Lot Number Three (3) in Block Number One (1) in Arlington Place; running thence North a distance of One Hundred Fourteen (114) feet and to the Northeast corner of said Lot Number Three (3) in Block Number One (1) in Arlington Place; running thence West over and along the North line of said Lot Number Three (3) in Block Number One (1) in Arlington Place a distance of Four Hundred (400) feet, more or less, to the place of beginning.

SUBJECT TO the real estate taxes for the year 1993, due and payable in May and November, 1994, and all subsequent taxes and assessments.

In Witness Whereof, Grantor has executed this Warranty Deed this 2nd day of June, 1993.


PETER DVORAK



Description:

A part of the Northeast quarter of the Northwest quarter and a part of the Southeast quarter of the Northwest quarter both of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point on the South line of the Northeast quarter of the Northwest quarter of said section 29, and 963.74 feet West of the Southeast corner of the Northeast quarter of the Northwest quarter; thence South 05 degrees 51 minutes East for 15.08 feet, thence West for 321.46 feet and to the East right-of-way of State Road # 46, thence North along the said road right-of-way for 95.00 feet, thence East for 311.71 feet, thence South 05 degrees 51 minutes East for 80.43 feet and to the point of beginning. Containing in all 0.69 acres, more or less.

Description: Easement

A part of the Northeast quarter of the Northwest quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point 80.00 feet North and 1283.66 feet West of the Southeast corner of the said quarter quarter and on the East right-of-way of State Road # 46; thence East for 311.71 feet; thence South 05 degrees 51 minutes East for 9.05 feet; thence West for 268.54 feet; thence South 77 degrees 49 minutes West for 45.01 feet and to the East right-of-way of State Road # 46; thence North on said right-of-way for 18.50 feet and to the point of beginning.

Engineer's Certification:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.



Raymond Graham
 Raymond Graham
 P.E. 8409 L.S. 9978
 3215 N. Smith Pike
 Bloomington, Indiana
 July 18 1980

Ph. 8535

Sec 29

Z.W. BRUNNEMER

811 ANITA

22603

CLIFFORD BYRD

Blountingten.

A part of the S.W. $\frac{1}{4}$ of Sec. 29, Township 9 North, Range 1 West, described as follows: Beginning at a point on the center line of the concrete pavement of State Highway No. 46 as now constituted, 280 feet Northwestwardly along said center line 70 feet due North of S.E. corner of the S.W. $\frac{1}{4}$ of said Sec.; running thence northward along said center line 515 feet (passing from the curve to the tangent at 400 feet); running thence E. 304 feet; running thence 423 feet to the place of beginning; excepting a tract in the Northwest corner thereof described as follows, to wit: Beginning at the Northwest corner of the above described tract, running thence East 262 feet, thence South 75 feet, thence West parallel with said North boundary line to the place of beginning. Subject to the easement of the public to travel on said Highway.



Public Easement

Public Easement

811 Anita


22603

882

Blgtn Twp. Sec 29-SW $\frac{1}{4}$
April, 1955

Blythe Yip Wiley to Hadley

Sec 29



PT. of BEGINNING:
1647.30' W AND 491.00' S
OF NE CORNER SEC 29,
T9N, R1W.

SCALE:
1" = 33.3'
NOV. 4, 1977


LOT No. 21
WILLIS WILEY
FLAT

DESCRIPTION: A part of the Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows; Beginning at the point that is 491.00 feet South and 1,647.30 feet West of the Northeast corner of said Section 29, thence South for 130.00 feet; thence West for 110.00 feet; thence North for 130.00 feet; thence East for 110.00 feet and to the point of beginning; Containing 0.33 acres more or less.


ENGINEER'S CERTIFICATION: I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any other encroachments from any other property on said surveyed property.

Raymond C. Graham

RAYMOND GRAHAM
INDIANA R.P.E. # 8409
3215 NORTH SMITH PIKE
BLOOMINGTON, INDIANA 47401




RETRACEMENT SURVEY SECTION 29, T9N, R1W BLOOMINGTON, IN.



C.D. Graham
C.D. GRAHAM L.S. 950014 INDIANA
615 W. KIRKWOOD AVE. BLOOMINGTON, INDIANA
OCTOBER 25, 2001 JOB NO. 01-472

- LEGEND:
- ⊗ = METAL FENCE POST SET ± 4'
 - = 5/8" REBAR SET FLUSH THIS SURVEY GRAHAM P.C. 9800014
 - ⊗ = METAL FENCE POST & REBAR W/CAP GRAHAM P.C. 9800014 HEIGHTS ARE SAME AS ABOVE



29-9-1W

More Particularly Described:
A part of the South half of Section 29, Township 9 North, Range 1 West, in Monroe County, Indiana, described as follows: Commencing at a Railroad spike found at the South East corner said Section 29, thence South 89 degrees 52 minutes 51 seconds West (basis of bearing) for 1771.06 feet to the East line of a public street right-of-way (North Willis Avenue), thence along said East line North 00 degrees 05 minutes 18 seconds for 1025.93 feet to the point of beginning, thence leaving said East line of right-of-way North 89 degrees 38 minutes 17 seconds East 124.35 feet, thence South 00 degrees 05 minutes 18 seconds West for 386.97 feet, thence South 89 degrees 38 minutes 17 seconds West for 124.35 feet and to the East line of said Street right-of-way; thence along said East line of said right-of-way North 00 degrees 05 minutes 18 seconds East for 386.97 feet and to the point of beginning.
Containing 1.11 acres

Exhibit "A"

TRI CO SURVEYING & MAPPING


Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305
103 West Temperance

P. O. Box 96
Ellettsville, Indiana 47429


Sec 29

SCALE: 1" = 100'



Sec 29

I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on December 5, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.



FILED
MAY 27 1982

V. Simpson
Auditor Monroe County, Indiana

A part of the East Half of the Southwest Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning North Zero (00) Degrees and Twenty-one (21) Minutes East 1087.50 feet from the Southwest Corner of said Half Quarter Section, at a Re Bar on the West Line of said Half Quarter Section, thence continuing along said West Line North Zero (00) Degrees and Twenty-one (21) Minutes East 80.00 feet, to a Re Bar, thence leaving said West Line North Eighty-nine (89) Degrees and Thirty-eight (38) Minutes East 379.84 feet to the center line of a stone drive, thence along said center line North Eighty-seven (87) Degrees and Forty (40) Minutes East 145.24 feet to a PK nail in the center line of State Road Number Forty-six (46), thence leaving said drive center line and along the center line of said State Road South Fifteen (15) Degrees and Forty-four (44) Minutes East 82.19 feet to a PK nail, thence leaving said center line and along an existing fence the following courses and distances: North Eighty-nine (89) Degrees and Fifty-two (52) Minutes West 119.00 feet to a post, thence South Zero (00) Degrees and Fourteen (14) Minutes East 10.50 feet to a post, thence North Eighty-nine (89) Degrees and Fifty-two (52) Minutes West 428.76 feet to the place of beginning.

Containing 1.00 acres, more or less.

SUBJECT TO: a Twelve (12) feet wide Easement, described as follows: Beginning at the PK nail in the center line of the aforementioned State Road, said point being the Northeast Corner of the above described 1.00 acres tract of land, thence running twelve feet Southerly of the North line of said tract at the bearing and distance of South Eighty-seven (87) Degrees and Forty (40) Minutes West 145.24 feet.

ALSO: a Twelve (12) feet wide Easement, described as follows: Beginning at a PK nail in the center line of the aforementioned State Road, said point being the Northeast Corner of the above described tract of land, thence running twelve feet Northerly of the North Line of said tract at the bearing and distance of South Eighty-seven (87) Degrees and Forty (40) Minutes West 145.24 feet.

TRI CO SURVEYING & MAPPING



Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305
103 West Temperance

P. O. Box 96
Ellettsville, Indiana 47429 +

+(200)
35 + 45 + ca. 10 + 145 to ell + other side

SCALE: 1" = 100'



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on December 5, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.

Edmund O. Farkas

Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

A part of the East Half of the Southwest Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning at a Re Bar on the West Line of said Half Quarter Section, said point being North Zero (00) Degrees and Twenty-one (21) Minutes East 1167.50 feet from the Southwest Corner of said Half Quarter Section, thence along said West Line North Zero (00) Degrees and Twenty-one (21) Minutes East 64.00 feet to a post, thence leaving said West Line South Eighty-nine (89) Degrees and Fifty-two (52) Minutes East 509.23 feet to the center line of State Road Number Forty-six (46), thence along said center line South Fifteen (15) Degrees and Forty-four (44) Minutes East 56.63 feet to a PK nail and to the center line of a stone drive, thence leaving said State Road center line and along said drive center line South Eighty-seven (87) Degrees and Forty (40) Minutes West 145.24 feet, thence leaving said center line South Eighty-nine (89) Degrees and Thirty-eight (38) Minutes West 379.84 feet to the place of beginning.

Containing 0.72 acres, more or less.

SUBJECT TO: a Twelve (12) feet wide Easement, described as follows: Beginning at the Pk nail in the center line of aforementioned State Road, said point also being the Southeast Corner of the above described tract of land, thence running twelve feet Northerly of the South Line of said tract at the bearing of South Eighty-seven (87) Degrees and Forty (40) Minutes West and distance of 145.24 feet.


ALSO: a Twelve (12) feet wide Easement, described as follows: Beginning at the Pk nail in the center line of aforementioned State Road, said point also being the Southeast Corner of the above described tract of land, thence running twelve feet Southerly of the South Line of said tract at the bearing and distance of South Eighty-seven (87) Degrees and Forty (40) Minutes West 145.24 feet.

RS
Zoning -
MSH can be replaced with me measure
equivalent, but can be no-north of
within 6' was. 10-10-79



Scale 1" = 30 ft

BASE OF BEARING: ASSUMED



REPORT OF SURVEY

In accordance with Title 36S, Chapter 12 of the Indiana Administrative Code, a report of survey is required to explain procedures used in establishing the subject property lines and to provide an opinion regarding uncertainties in surveyed property lines.

The following procedures were used to establish the subject property lines.

1. The subject property consists of four remnant parcels of real estate, combined by this survey into two parcels. Tract A is three parcels being combined into one tract. Tract B is a part of Lot 1 in Arlington Place Subdivision, a subdivision platted in 1916. The legal descriptions of both parcels are tied to the south line of Lot 1.
2. The south line of Lot 1 was established by best fit of three monuments found.
3. The right-of-way for State Road 46 was established from right-of-way monuments found.
4. The remaining lines of both Tract A and Tract B were established at dead dimensions and angles.

Uncertainties in the boundary positions may result from any or all of the following factors:

A. Availability and Condition of Reference Monuments

Found monuments were generally in good condition.

B. Ambiguities in Record Description

The plat of Arlington Place does not have a north-south dimension for Lots 1, 2, and 3. Dead information point to a dimension of 114.9 feet for these lots and the deads for the current parcelization of this lot reflect this number.

Some dimensional ambiguities exist for Tract A and B's southern and eastern adjacencies. At one time, these tracts were under one ownership and review of current and historical deeds reveal the current owner is entitled to what is left.

C. Inconsistencies in Lines of Occupation

No inconsistencies were found.

D. Theoretical Uncertainty

Due to random errors caused by survey instrument precision and survey field methods used, the theoretical uncertainty of all points in this survey is 0.28 feet, which meets the requirements of a Class 'B' survey as defined in the survey standards. This means that the actual field position of all points in this survey is within this uncertain distance from the theoretical point locations as shown on the survey plat.

I, Richard E. Waltrip, Indiana LSP#500010, hereby certify that the attached plat and legal description represents a Class "B" survey in accordance with survey standards set forth in Title 36S, Chapter 12 of the Indiana Administrative Code and in witness thereof I have set my hand and seal this _____ day of _____, 1997.

Richard E. Waltrip, LSP#500010
Byrum Farny & Associates, Inc.
538 North Walnut Street
Bloomington, Indiana 47404
(812) 332-8080




OWNER: L. PAUL BEYERS

L. PAUL BEYERS TRACT
PART OF SECTION 29
TOWNSHIP 9 N, RANGE
MONROE COUNTY, INDI
PLAT OF SURVEY

DRAWING NO. IN
SHEET 1 of 1

PREPARED BY BYNUM FARNY & ASSOCIATES INC.

538 N. WALNUT ST. BLOOMINGTON, IN. 47404 (812)332-



LEGAL DESCRIPTION
TRACT "A"

A part of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

Commencing at the Southeast corner of said section thence along the south line of said section North 90 degrees 00 minutes 00 seconds West 2542.27 feet; thence leaving said south line North 00 degrees 50 minutes 46 seconds West 1021.82 feet; thence South 89 degrees 58 minutes 36 seconds West to the Southeast corner of Lot No. 1 of Block No. 1 in Arlington Place as recorded in Plat Cabinet "B", Envelope 36 in the Office of the Recorder of Monroe County, Indiana, 250.80 feet; thence along the south line of said lot South 89 degrees 50 minutes 04 seconds West 309.75 feet to the point of beginning; thence continuing along said line South 89 degrees 50 minutes 04 seconds West to the centerline of the Old Bloomington and Ellettsville Road 294.25 feet; thence along said centerline South 28 degrees 50 minutes 17 seconds East 101.93 feet; thence leaving said centerline North 75 degrees 45 minutes 09 seconds East 152.10 feet; thence North 89 degrees 50 minutes 04 seconds East 101.05 feet; thence North 03 degrees 42 minutes 13 seconds West 52.53 feet to the point of beginning, containing 0.41 acres, more or less.

Subject to a 30 foot half right-of-way for State Road 46.

LEGAL DESCRIPTION
TRACT "B"

A part of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

Commencing at the Southeast corner of said section thence along the south line of said section North 90 degrees 00 minutes 00 seconds West 2542.27 feet; thence leaving said south line North 00 degrees 50 minutes 46 seconds West 1021.82 feet; thence South 89 degrees 58 minutes 36 seconds West to the Southeast corner of Lot No. 1 of Block No. 1 in Arlington Place as recorded in Plat Cabinet "B", Envelope 36 in the Office of the Recorder of Monroe County, Indiana, 250.80 feet; thence along the south line of said lot South 89 degrees 50 minutes 04 seconds West 309.75 feet to the point of beginning; thence continuing along said line South 89 degrees 50 minutes 04 seconds West 102.25 feet; thence leaving said south line North 01 degrees 46 minutes 44 seconds East 100.04 feet; thence North 89 degrees 50 minutes 04 seconds East 92.67 feet; thence South 03 degrees 42 minutes 13 seconds East 100.16 feet and to the point of beginning, containing 0.22 acres, more or less.

Blyth Sec 29 & Arlington Place Lot 1

REPORT OF SURVEY

In accordance with Title 865, Chapter 12 of the Indiana Administrative Code, a report of survey is required to explain procedures used in establishing the subject property lines and to provide an opinion regarding uncertainties in surveyed property lines.

The following procedures were used to establish the subject property lines.

1. The subject property consists of four remnant parcels of real estate, combined by this survey into two parcels. Tract A is three parcels being combined into one tract. Tract B is part of Lot 1 in Arlington Place Subdivision, a subdivision platted in 1916. The legal descriptions of both parcels are tied to the south line of Lot 1.
2. The south line of Lot 1 was established by best fit of three monuments found.
3. The right-of-way for State Road 46 was established from right-of-way monuments found.
4. The remaining lines of both Tract A and Tract B were established at deed dimensions and angles.

Uncertainties in the boundary positions may result from any or all of the following factors:

A. Availability and Condition of Reference Monuments

Found monuments were generally in good condition.

B. Ambiguities in Record Description

The plat of Arlington Place does not have a north-south dimension for Lots 1, 2, and 3. Deed information point to a dimension of 114.9 feet for these lots and the deeds for the current parcelization of this lot reflects this number.

Some dimensional ambiguities exist for Tract A and it's southern and eastern adjoiners. At one time, these tracts were under one ownership and review of current and historical deeds reveal the current owner is entitled to "what is left."

C. Inconsistencies in Lines of Occupation

No inconsistencies were found.

D. Theoretical Uncertainty

Due to random errors caused by survey instrument precision and survey field methods used, the theoretical uncertainty of all points in this survey is 0.25 feet, which meets the requirements of a Class "B" survey as defined in the survey standards. This means that the actual field position of all points in this survey is within this uncertain distance from the theoretical point locations as shown on the survey plat.

NUTHEAST CORNER OF LOT 1
BLOCK 1 IN ARLINGTON
PLACE SUBDIVISION
3/4" PIPE FND.

89°58'36"W
250.80'

3/4" PIPE FND.

Tract A & B

N00°50'46"W 1021.82'

N90°00'00"W
2542.27'

SOUTHEAST CORNER OF
SECTION 29, T-9-N, R-1-W
RAILROAD SPIKE FND.

I, Richard E. Waltrip, Indiana L529500010, hereby certify that the attached plat and legal description represents a Class "B" survey in accordance with survey standards set forth in Title 865, Chapter 12 of the Indiana Administrative Code and in witness thereof I hereunto attach my hand and seal this 25th day of August, 1997.

Richard E. Waltrip

Richard E. Waltrip, L529500010
Bynum Fanyo & Associates, Inc.
528 North Walnut Street
Bloomington, Indiana 47404
(812) 332-8030

Blotn
Sec 29
Arlington Place

BLOOMINGTON ENGINEERING COMPANY

ENGINEERS and SURVEYORS
811 ANITA STREET
BLOOMINGTON, INDIANA 47401
Phone 332-2603



Sheet 1 of 2

Wayne Johnson Descriptions

Tract 1

A part of the Southeast quarter of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, described as follows:


Beginning at a point that is 11.25 feet South and 520.88 feet West of the Southeast corner of the said quarter section, said point being in the centerline of State Road 46 and in the South line of said quarter section, thence $S88^{\circ}45'47''W$, 50 feet along the centerline of State Highway 46, and to a point on the West line of North Jackson Street, if extended, thence $N00^{\circ}26'49''E$ for a distance of 197.70 feet, thence $S88^{\circ}49'55''W$ for a distance of 144.60 feet, thence $S00^{\circ}26'49''W$ for a distance of 41.70 feet, thence $S88^{\circ}49'55''W$ for a distance of 231.18 feet, thence $N00^{\circ}02'35''E$ for a distance of 210.90 feet thence $N89^{\circ}01'11''W$ for a distance of 132.10 feet, thence $N00^{\circ}23'54''W$ for a distance of 759.23 feet, thence $S89^{\circ}07'36''E$ for a distance of 878.49 feet, thence $S00^{\circ}03'13''W$ for a distance of 918.20 feet, thence $N89^{\circ}20'13''W$ for a distance of 260.48 feet, thence $S00^{\circ}26'49''W$ for a distance of 197.70 feet, and to the place of beginning. Containing 18.49 acres, more or less.


Subject to the right-of-way of Indiana State Highway 46.

Subject to Sewer Line Easements granted to the City of Bloomington, Indiana.

DESCRIPTION PREPARED FROM A SURVEY
CONDUCTED BY MID-STATES ENGINEERING CO.,
143 EAST CHICAGO ST., INDIANAPOLIS, INDIANA,
CERTIFIED BY M. N. FRANKLIN, REGISTRY #
8620, AND DATED, OCTOBER 1963.

ROBERT W. BRUNNER
REGISTERED LAND SURVEYOR
INDIANA REGISTRY #5512
12 JUNE 1972





50.000

1.56A

1.12A

1.00A

1.00A

1257 to 1258

(812) 334-8941

ARCHER
ASSOCIATES, INC.

P. O. Box 1296
Bloomington, IN 47402

LAND SURVEYING

SURVEYOR LOCATION REPORT


THIS REPORT IS DESIGNED FOR USE BY A TITLE INSURANCE COMPANY WITH RESEDENTIAL LOAN POLICIES. NO CORNER MARKERS WERE SET AND THE LOCATION DATA HEREIN IS BASED ON LIMITED ACCURACY MEASUREMENTS. THEREFORE, NO LIABILITY WILL BE ASSUMED FOR AND USE OF THIS DATA FOR CONSTRUCTION OF NEW IMPROVEMENTS OR FENCES.

PROPERTY ADDRESS: 2704 Arlington Road, Bloomington, Indiana 47404

PROPERTY DESCRIPTION: See attached legal description.

CLIENT I.D. NO.:

Subject tract is not located in a flood hazard area.



TITLE CO.:

I HEREBY CERTIFY TO THE PARTIES NAMED ABOVE THAT THE REAL ESTATE DESCRIBED HEREIN WAS INSPECTED UNDER MY SUPERVISION ON THE DATE INDICATED AND THAT, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS REPORT CONFORMS WITH THE REQUIREMENTS CONTAINED IN SECTIONS 42 THROUGH 44 OF 864 IAC 1.1-13 FOR A SURVEYOR LOCATION REPORT. THE ACCURACY OF ANY FLOOD HAZARD STATEMENT SHOWN ON THIS REPORT IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP.

DATE OF SURVEY:


4/13/99

REGISTERED LAND SURVEYOR'S SIGNATURE:

Steven W. Archer

PROPOSED BUYER:

PROPOSED LENDER:





ARCHER

AND ASSOCIATES, INC.

(812) 334-8941

P. O. Box 1296

Bloomington, IN 47402


LAND SURVEYING

A part of the Northwest quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows: Beginning 725.12 feet South and 1077.33 feet West (727.98 feet South and 1090 feet West) from the Northeast corner of said quarter section; thence South Eighty-five (85) degrees, Forty (40) minutes West 270.48 feet (Deed description 270.00 feet West) to an old road bed; thence on said road bed North Twenty-five (25) degrees, Fifty-seven (57) minutes, Thirty-six (36) seconds West 15.67 feet; thence North Fifty-five (55) degrees, Twenty-seven (27) minutes, Fifty-six (56) seconds East 138.27 feet; thence on an existing fence line South Eighty-five (85) degrees, Three (03) minutes, Twenty-four (24) seconds East 162.90 feet to a post; thence South Zero (00) degrees, Twenty-two (22) minutes, Eight (08) seconds East 58.00 feet to the point of beginning. Containing 0.39 acres, more or less.

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
 P.O. Box 96
 Ellettsville, Indiana 47429
 Phone: 812-876-2305



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on May 14, 1984; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.

Edmund O. Farkas
 Registered Land Surveyor
 Ind. Reg. No. 50114

A part of the Southeast Quarter of the Northwest Quarter of Section Twenty-nine (29), Township Nine (9) North, Range One (1) West, Monroe County, Indiana and more particularly described as follows:

Beginning 987.33 feet North and 848.00 feet West from the center of said Section 29 at a stone found, thence West 248.72 feet to a rebar, thence North Five (05) Degrees, Eleven (11) Minutes, Nineteen (19) Seconds East 75.51 feet to a rebar, thence South Eighty-nine (89) Degrees, Fifty-seven (57) Minutes, Nine (09) Seconds East 241.88 feet to a rebar, thence South 75.00 feet to the point of beginning.

Containing 0.42 acres, more or less.


FILED

NOV 26 1984

Sue Stinson
 Auditor Monroe County, Indiana


23/4/12
 83/16

Page 29




SCALE: 1" = 50'

ST. RD. 46/ARLINGTON ROAD



6" x 6" STONE w/"X" FOUND
924' NORTH OF & 848' WEST
OF THE SE CORNER OF THE
NW 1/4, SEC. 29, T 9 N, R 1 W,
MONROE COUNTY, INDIANA
AS RECORDED IN DEED RECORD
192, PAGE 61.



June 13, 2005
Douglas R. Curry

• REBAR w/CAP SET THIS SURVEY

RADER BOUNDARY
PT. OF SEC. 29, T 9 N, R 1 W,
MONROE COUNTY, INDIANA
JOB NO. 5005071

WARRANTY DEED

THIS INDENTURE WITNESSETH, That EDWIN BENNETT, HELEN C. YATES, and ED BENNETT STONE CO., of Monroe County, Indiana, CONVEY AND WARRANT to STAR QUARRY, INC., an Indiana Corporation, of Monroe County, Indiana, for and in consideration of One Dollar (\$1.00) and other good and valuable consideration not expressed herein, the receipt whereof is hereby acknowledged, the following described real estate in Monroe County, Indiana, to-wit:

A part of the East Half of Section Thirty (30), a part of the West Half of the Northwest Quarter of Section Twenty-nine (29), and a part of the Northwest Quarter of the Northeast Quarter of Section Thirty-one (31), all in Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows: Beginning South Zero (00) degrees Twenty-two (22) minutes Thirty (30) seconds East 803.35 feet from the Northeast corner of said Section Thirty (30), and on the East line of said Section; thence North Eighty-nine (89) degrees Forty-four (44) minutes Twenty-three (23) seconds East 390.01 feet to the West right of way line of State Road 37 North; thence on the said Right of way line the following courses and distances: South Seven (07) degrees Seven (07) minutes Thirty-one (31) seconds West 390.94 feet; thence South Seven (07) degrees Fifty-six (56) minutes Thirty-five (35) seconds East 347.55 feet; thence South Four (04) degrees Thirty-three (33) minutes Twenty-one (21) seconds West 449.81 feet; thence South Nineteen (19) degrees Fifty-eight (58) minutes Forty-eight (48) seconds West 200.72 feet; thence Southwesterly 1005.40 feet along an arc to the right having the radius of 7449.44 feet and subtended by a long chord having a bearing of South Eleven (11) degrees Thirty-eight (38) minutes Thirty-one (31) seconds West and length of 1004.64 feet; thence South Fifteen (15) degrees Thirty (30) minutes Thirty (30) seconds West 168.95 feet; thence South One (01) degree Twenty-eight (28) minutes Twenty-eight (28) seconds West 103.08 feet; thence South Fifteen (15) degrees Thirty (30) minutes Thirty (30) seconds West 64.13 feet to the East line of said Section Thirty (30); thence South Fifteen (15) degrees Thirty (30) minutes Thirty (30) seconds West 386.41 feet; thence leaving the said right of way line North Eighty-nine (89) degrees Thirty-one (31) minutes Forty-two (42) seconds West 719.24 feet (Deed distance 708.6 feet) to a rebar; thence South Zero (00) degrees Twenty-two (22) minutes Thirty (30) seconds East 526.78 feet to a rebar; thence South Eighty-nine (89) degrees Seventeen (17) minutes Fifty-four (54) seconds West 512.16 feet to an iron pipe, and to the West line of the Southeast Quarter of the Southeast Quarter of said Section Thirty (30); thence on the said line South Zero (00) degrees Twenty (20) minutes Fifty-one (51) seconds East 940.08 feet to the Southwest corner of said Southeast Quarter of the Southeast Quarter; thence North Eighty-nine (89) degrees Twenty-two (22) minutes Forty-nine (49) seconds West on the South line of said Section Thirty (30) 555.31 feet to the West right of way line of the railroad switch; thence on the said right of way line South Thirty-two (32) degrees Thirteen (13) minutes Twenty (20) seconds West 61.38 feet (Deed distance 64.0 feet) to the centerline of Vernal Pike; thence on the said centerline North Sixty-nine (69) degrees Four (04) minutes Fifty-two (52) seconds West 146.09 feet; thence leaving the said centerline North Eighty-five (85) degrees Fifty-one (51) minutes Forty-five (45) seconds East 19.24 feet to the said South Section line 150 feet Westerly from the said West railroad right of way line; thence on the said Section line North Eighty-nine (89) degrees Twenty-two (22) minutes Forty-nine (49) seconds West 31.80 feet to the centerline of said Vernal Pike; thence on the said centerline the following courses and distances: North Forty-six (46) degrees Eight (08) minutes Thirty-four (34) seconds West 444.44 feet; thence North Forty-five (45) degrees Twenty-three (23) minutes Thirty-five (35) seconds West 397.96 feet to the West line of said East Half of said Section Thirty (30); thence North Zero (00) degrees Nineteen (19) minutes Thirteen (13) seconds West 2066.78 feet to the center of said Section Thirty (30); thence North Zero (00) degrees Nineteen (19) minutes Thirteen (13) seconds West on the said West line 1053.35 feet; thence leaving the said West line North Fifty-nine (59) degrees Five (05) minutes Four (04) seconds East 1551.34 feet (Deed distance 1541.76 feet) to a rebar; thence North Eighty-nine (89) degrees Forty-four (44) minutes Twenty-three (23) seconds East 1335.35 feet to the place of beginning. Containing 236.60 acres, more or less.

Bloomington Ind. Dec 19, 1931
Bennett Stone Co. to Star Quarry

11 ✓
12 ✓
38 ✓
36 ✓
18 ✓
16 ✓
15 ✓
7 ✓
6 ✓

9
10

Y5

EXCEPTING A part of the Southeast Quarter of Section Thirty (30), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows: Beginning 607.8 feet Westerly from the Northeast corner of said Quarter Section; thence South Zero (00) degrees Ten (10) minutes Forty-nine (49) seconds West 535.00 feet; thence South Eighty-three (83) degrees Forty (40) minutes Forty-nine (49) seconds West 204.50 feet; thence North Eighty-eight (88) degrees Forty-nine (49) minutes Eleven (11) seconds West 302.90 feet; thence South Sixty-eight (68) degrees Forty (40) minutes Forty-nine (49) seconds West 221.40 feet; thence South Fifty-three (53) degrees Ten (10) minutes Forty-nine (49) seconds West 98.90 feet; thence South Thirty-three (33) degrees Ten (10) minutes Forty-nine (49) seconds West 95.60 feet; thence North Six (06) degrees Forty-four (44) minutes Twenty-eight (28) seconds East on the East right of way line of the main switch of the C. I. & L. railroad 778.80 feet to the North line of said Quarter Section; thence South Eighty-nine (89) degrees Forty-nine (49) minutes Eleven (11) seconds East 754.10 feet to the place of beginning.

ALSO EXCEPTING, a part of the Northeast Quarter of said Section Thirty (30), and more particularly described as follows: Beginning on the South line and 1111.9 feet Westerly from the Southeast corner of said Quarter Section; thence North Zero (00) degrees Twenty-two (22) minutes Thirty (30) seconds West 200.00 feet; thence North Eighty-nine (89) degrees Forty-nine (49) minutes Eleven (11) seconds West 170.00 feet to the East right of way line of said railroad; thence on the said right of way line South Twenty-one (21) degrees Thirty (30) minutes Eight (08) seconds West 214.69 feet; thence South Eighty-nine (89) degrees Forty-nine (49) minutes Eleven (11) seconds East 250.00 feet to the place of beginning. Containing 11.47 acres, more or less.

Containing in all after these exceptions 225.13 acres, more or less.

ALSO, a Thirty (30) foot wide Easement in the Northeast Quarter of the Northeast Quarter of Section Thirty (30), Township Nine (9) North, Range One (1) West, Monroe County, Indiana, said Easement being Fifteen (15) feet on both sides of the under-described centerline:

Beginning at the Northwest corner of said Quarter Quarter Section; thence along the North line of said Quarter Quarter Section and along a county road North Eighty-nine (89) degrees Forty-four (44) minutes Twenty-three (23) seconds East 233.38 feet to the true point of beginning; thence leaving said North line and said county road and along said 30 foot wide Easement centerline the following courses and distances: South Zero (00) degrees Eight (08) minutes Twenty (20) seconds East 151.64 feet; thence South Two (02) degrees Zero (00) minutes Fifty-nine (59) seconds East 546.97 feet; thence South Forty-one (41) degrees Twenty-nine (29) minutes Ten (10) seconds West 126.70 feet; thence South Twenty-seven (27) degrees Forty-four (44) minutes Ten (10) seconds West 11.86 feet.

Subject to a Telephone Line Easement to Indiana Bell Telephone Company recorded April 30, 1929, at page 155 of Miscellaneous Record 12 in the office of the Recorder of Monroe County, Indiana.

Subject to a Transmission Line Easement to Public Service Company recorded March 15, 1939, at page 448 of Miscellaneous Record 19 in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement to Public Service Company of Indiana, Inc., recorded February 14, 1951, at pages 413 and 414 of Deed Record 109 in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement to Public Service Company of Indiana, Inc., recorded Muly 15, 1968, at pages 10 and 11 of Deed Record 185 in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement to Public Service Company of Indiana, Inc., recorded October 1, 1970, at pages 483 and 484 of Deed Record 198 in the office of the Recorder of Monroe County, Indiana.

Subject to a Water Line Easement to Calvin K. Summitt, Jr. and Edna Summitt, recorded February 16, 1971, at pages 186 through 188 of Deed Record 210 in the office of the Recorder of Monroe County, Indiana.

Water Line Easement to Roger Carter and Helen Carter, husband and wife, recorded April 22, 1971, at pages 522 and 523 of Deed Record 202 in the office of the Recorder of Monroe County, Indiana.

Subject to an Easement for Water Line to the City of Bloomington, Indiana, recorded September 21, 1966, at page 459 of Miscellaneous Record 60 in the office of the Recorder of Monroe County, Indiana.

Oil and Gas Lease to Ohio Oil & Gas recorded August 3, 1981, at pages 501 and 502 of Oil and Gas Lease Record 3; assigned to Jones-Kimco Leasehold Partnership by Assignment recorded May 20, 1982, at pages 379 through 392 of Release and Assignment Record 46; and modified by Agreement recorded December 3, 1984, at pages 122 through 124 of Miscellaneous Record 153 all in the office of the Recorder of Monroe County, Indiana.

Subject to a Utility Easement to Indiana Bell Telephone Company, Incorporated, recorded January 31, 1985, at page 365 of Deed Record 312 in the office of the Recorder of Monroe County, Indiana.

Subject to a Grant of Easement and Right-of-way to Bloomington Packing Company, Inc., recorded July 26, 1985, at pages 521 and 522 of Deed Record 316 in the office of the Recorder of Monroe County, Indiana.

Subject to a Right-of-way conveyed to Indianapolis, Bloomington and Bedford Railroad Company recorded June 2, 1984, at pages 93 through 95 of Miscellaneous Record 4 in the office of the Recorder of Monroe County, Indiana.

Subject to any rights that John P. Tourner may have in the real estate to locate and operate a switch across a part of the above described real estate as set out in Deed recorded June 5, 1956, at pages 353 and 354 of Deed Record 120 in the office of the Recorder of Monroe County, Indiana.

Subject to the permanent extinguishment of all rights and easements of ingress to, from and across the limited access facility, to be known as State Road 37 and State Road 46 and as projects F-123(11), F-893(7) and F-428(17) to and from the owner's abutting lands only along the line described in the Deed from Indiana Limestone Company, Inc., to the State of Indiana, recorded January 25, 1972, at pages 365 through 369 of Deed Record 209 in the office of the Recorder of Monroe County, Indiana.

IN WITNESS WHEREOF, the said EDWIN BENNETT, HELEN C. YATES, and ED BENNETT STONE CO., have hereunto set their hands and seals this 2nd day of ~~October~~ ^{May} 1988. 1989.

Edwin Bennett
EDWIN BENNETT

Helen C. Yates
HELEN C. YATES

ED BENNETT STONE CO.

by: Edwin Bennett
EDWIN BENNETT


STATE OF INDIANA, MONROE COUNTY, SS:

Before me, the undersigned, a Notary Public, in and for said County and State, this 2nd day of May, 1989, personally appeared the within named EDWIN BENNETT, HELEN C. YATES, and ED BENNETT STONE CO., by EDWIN BENNETT, Grantors in the above and foregoing Warranty Deed and acknowledged the execution of the same to be their vountary act and deed, for the uses and purposes mentioned, and also swore to the truth of all statements made in this deed.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my official seal.

My commission expires:

June 6, 1989



Peggy J. Ragle, Notary Public
residing in Monroe County, Indiana

This instrument prepared by: WILLIAM B. REAM, LAWYER

Send Tax Duplicate to:

2101 Hunter Lane
Bloomington, Indiana
47401

CORNER of the
1/4 of SEC. 30

200.72'

STAR QUARRY SURVEY

0.45 ACRES IN SEC. 31
15.31 ACRES IN SEC. 29
209.37 ACRES IN SEC. 30
TOTAL ACREAGE: 225.13 ACRES ±

S 11° 38' 31" W 1004.64'
WEST R/W OF HWY. 37 BYPASS

S 15° 30' 30" W
168.95'

S 01° 28' 28" W
103.08'

S 15° 30' 30" W
64.13'

S 15° 30' 30" W
386.41'


719.24'


REBAR (SET)

PLAT PREPARED BY:

Edmund O. Farkas

EDMUND O. FARKAS
REG. LAND SURVEYOR
IND. REG. NO. S0114





DESCRIPTION

A part of the Northeast quarter of Section 29, Township 9 North, Range 1 West Monroe County, Indiana, being more particularly described as follows:

Commencing at the Southwest corner of said Northeast quarter; thence SOUTH 89 degrees 59 minutes 53 seconds East (assumed basis of bearings) 430.75 feet; thence NORTH 00 degrees 00 minutes 00 seconds East a distance of 700.16 feet; thence SOUTH 88 degrees 30 minutes 19 seconds East a distance of 126.96 feet; thence NORTH 00 degrees 00 minutes 02 seconds East a distance of 268.09 feet; thence NORTH 90 degrees 00 minutes 00 seconds East a distance of 65.00 feet; thence SOUTH 81 degrees 54 minutes 53 seconds East a distance of 40.40 feet; thence NORTH 90 degrees 00 minutes 00 seconds East a distance of 4.60 feet to the West right of way of Stone Lake Drive and a non tangent curve to the right having a radius of 260.00 feet and a chord bearing and distance of NORTH 22 degrees 28 minutes 59 seconds East, 105.36 feet; thence Northerly along said curve through a central angle of 23 degrees 22 minutes 47 seconds for a length of 106.09 feet; thence NORTH 34 degrees 10 minutes 23 seconds East a distance of 7.78 feet to a tangent curve to the left having a radius of 200.00 feet and a chord bearing and distance of NORTH 18 degrees 18 degrees 52 minutes 30 seconds East, 105.54 feet; thence Northerly along said curve through a central angle of 30 degrees 35 minutes 46 seconds for a length of 106.80 feet; thence leaving the West line of Stone Lake Drive SOUTH 86 degrees 25 minutes 23 seconds East a distance of 49.93 feet to a tangent curve to the right having a radius of 99.00 feet and a chord bearing and distance of SOUTH 71 degrees 37 minutes 04 seconds East, 57.65 feet; thence Easterly along said curve through a central angle of 33 degrees 51 minutes 28 seconds for a length of 58.50 feet; thence SOUTH 54 degrees 41 minutes 20 seconds East a distance of 175.82 feet to a tangent curve to the left having a radius of 126.00 feet and a chord bearing and distance of NORTH 58 degrees 22 minutes 14 seconds East, 231.87 feet; thence Easterly and Northerly along said curve through a central angle of 133 degrees 52 minutes 51 seconds for a length of 294.42 feet; thence NORTH 08 degrees 33 minutes 54 seconds WEST a distance of 59.62 feet; thence SOUTH 78 degrees 03 minutes 18 seconds WEST a distance of 125.00 feet; thence NORTH 18 degrees 08 minutes 42 seconds EAST a distance of 213.89 feet; thence SOUTH 77 degrees 21 minutes 19 seconds EAST a distance of 143.37 feet to a non-tangent curve to the right having a radius of 126.00 feet and a chord bearing and distance of SOUTH 11 degrees 39 minutes 59 seconds WEST, 15.29 feet; thence Southerly along said curve through a central angle of 06 degrees 57 minutes 33 seconds for a length of 15.30 feet; thence SOUTH 15 degrees 08 minutes 46 seconds WEST a distance of 87.86 feet to a tangent curve to the left having a radius of 174.00 feet and a chord bearing and distance of SOUTH 03 degrees 17 minutes 25 seconds WEST, 71.49 feet; thence Southerly along said curve through a central angle of 23 degrees 42 minutes 38 seconds for a length of 72.01 feet to the Point of Beginning containing 0.63 acres, more or less.

This survey was executed according to survey requirements contained in Sections 1 through 19.


This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose.

Evidence of easements have not been located in the field and are not shown on this survey.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 11th day of October, 2010

Ben E. Bledsoe
Ben E. Bledsoe
Registered Land Surveyor No. S5099
State of Indiana



DECKARD LAND SURVEYING
1604 S. Henderson St.
Bloomington IN. 47401
(812) 961-0235

REVIEWED

By Cassidy Raley at 2:22 pm, Jan 08, 2018

**SURVEY DESCRIPTION FOR
KELLY COLLIER
JOB NO. 11-116
PEDESTRIAN EASEMENT**

A part of Block Number Four (4) in Arlington Place, being a sub-division of a part of Section 29, Township 9 North, Range 1 West, Monroe County, Indiana, being more particularly described as follows:


Beginning at the Southeast corner of said Block Number Four (4); thence along the south line of said Block 4 North 90 degrees 00 minutes 00 seconds West for a distance of 5.00 feet; thence leaving said south line North 00 degrees 16 minutes 37 seconds West for a distance of 150.11 feet to the north line of the subject property (Collier, Instr. 2016003739); thence along said north line North 89 degrees 49 minutes 09 seconds East for a distance of 5.00 feet to the Northeast corner of the subject property (Collier, Instr. 2016003739); thence along the east line of the subject property (Collier, Instr. 2016003739) South 00 degrees 16 minutes 37 seconds East for a distance of 150.13 feet to the Point of Beginning.


Subject to the right of way of N. Monroe Street and all easements of record.

The within survey was performed without the benefit of source of title and is subject to any statement of facts revealed by the same.

Subject to the above reservation, the survey work shown hereon was performed either by me or under my direct supervision and control and to the best of my knowledge and belief was performed according the survey requirements in 865 IAC 1-12-1 through 19.

Certified this 10 day of May, 2016.


Eric L. Deckard
Registered Land Surveyor LS29900012
State of Indiana




A PART OF BLOCK NUMBER 4 ARLINGTON
SECTION 29, TOWNSHIP 9 NORTH, RANGE 1 WEST
MONROE COUNTY, INDIANA

LEGEND

- STONE FOUND
- REBAR FOUND
- REBAR SET
- RR SPIKE FOUND
- PIPE FOUND
- FENCE
- MAG SPIKE SET
- RECORD
- MEASURED


NOTES:

- 1). Basis of bearing (Assumed).
- 2). Source of title Now or Formerly owned by Kelly Collier and Beverly Collier as found in Instrument Number 2016003739 in the office of the Monroe County Recorder.
- 3). Reference is made to a survey performed by Eric L. Deckard for Markaye Bleth dated October 4th, 2011.
- 4). Reference is made to a plat survey of Arlington Place (Plat Cabinet "B", Env. 36).
- 5). I affirm, under penalty for perjury, that I have taken responsible care to redact each Social Security number in this document, unless required by law.
- ERIC L. DECKARD



LOCATION MAP



PROJECT LOCATION



This drawing was prepared in the office without the benefit of a field survey and examination of adjoining deeds. This certification does not take into consideration additional facts that an accurate and correct title search and/or examination of a field survey might disclose.

Certified this 10 day of May, 2016.



Eric L. Deckard
Registered Surveyor LS29900012
State of Indiana




SCALE 1" = 50'

KELLY COLLIER		DECKARD LAND SURVEYING 1604 S. HENDERSON ST. BLOOMINGTON IN. 47401 (812)961-0235
PEDESTRIAN EASEMENT	SHEET 1 OF 2	
DRAWN BY: ERS DATED:05/09/16	CHECKED BY: ELD	PROJECT NO. 16-53


A PART OF
SEC. 29, 30 & 31
T-9-N, R-1-W.
MONROE COUNTY, INDIANA.



SCALE: 1" = 300'



CERTIFIED THIS 30th DAY OF OCTOBER, 2007



Douglas R. Curry
DOUGLAS R. CURRY
INDIANA L.S. NO. 890006
BYNUM FANYO & ASSOCIATES, INC.
528 N. WALNUT STREET, BLOOMINGTON, IN 47404
TELEPHONE (812) 332-8030
FAX (812) 339-2990

LOGAN LAND DEVELOPMENT, LLC
INST. NO. 2005019459

LOGAN LAND DEVELOPMENT, LLC
INST. NO. 2004003974

LO-AD LAND DEVELOPMENT, LLC
ST. NO. 2005019459

EAST LINE, SE 1/4,
NW 1/4, SEC. 30

STAR QUARRY, INC.
D.R. 359, P. 399

/4, NW 1/4, SEC. 30
LOGAN LAND DEVELOPMENT, LLC
INST. NO. 2004003974

STATE OF INDIANA
INST. NO. 2000002079
PARCEL ID 012-04660-01


STATE OF INDIANA
S.R. 46 RIGHT-OF-WAY
INSTRUMENT NO. 1999014286
PARCEL ID 012-03850-01

WEST LINE. SE 1/4, NW 1/4, SEC. 30


PT. OF STATE ROAD 46
PT. OF SEC. 19 & 30, T9N, R1W
& PT. OF SEC. 24, T9N, R2W,
MONROE COUNTY, INDIANA
PT. OF STATE HIGHWAY
PROJECT: NH-062-4(010)

DRAWING NO. 5006122
SHEET 1 OF

PREPARED BY BYNUM FANYO & ASSOCIATES INC. 528 N. WALNUT ST. BLOOMINGTON, IN. 47404



KEY MAP




KEY TO ABBREVIATIONS
R.W. = RIGHT OF WAY
U.E. = UTILITY EASEMENT
L.S. = LANDSCAPE EASEMENT
D.E. = DRAINAGE EASEMENT
C.L. = CENTER LINE
P.E. = PEDESTRIAN EASEMENT
S.G.B L.E. = SIGN, GATE, & LIGHT EASEMENT
A.E. = ACCESS EASEMENT

CURVE DATA TABLE					
#	RADIUS	DELTA	LENGTH	CH. DISTANCE	TANGENT
6	480.00'	14-07-40	110.98'	110.68'	68.76'

Lanam RidgeView Estates
SECTION I

PREPARED BY: SMITH NEUBECKER & ASSOCIATES INC.

JOB NO. 1540
3-14-95




KEY MAP

KEY TO ABBREVIATIONS

R.W. = RIGHT OF WAY
 U.E. = UTILITY EASEMENT
 L.S. = LANDSCAPE EASEMENT
 D.E. = DRAINAGE EASEMENT
 C. = CENTER LINE
 P.E. = PEDESTRIAN EASEMENT
 S.G. & L.E. = SIGN, GATE, & LIGHT EASEMENT
 A.E. = ACCESS EASEMENT

Scale: 1" = 100'



CURVE DATA TABLE					
#	RADIUS	DELTA	LENGTH	CH. DISTANCE	TANGENT
6	450.00'	29-14-59	229.73'	227.24'	117.43'

Lanam RidgeView Estates

SECTION I

PREPARED BY: SMITH NEUBECKER & ASSOCIATES INC.

JOB NO. 1540
3-14-95

PAGE 4 OF 5